

NEOGENE PALEONTOLOGY IN THE NORTHERN DOMINICAN REPUBLIC 16. THE FAMILY CORBULIDAE (MOLLUSCA: BIVALVIA)

LAURIE C. ANDERSON

Department of Geology and Geophysics, Louisiana State University,
Baton Rouge, Louisiana, 70803

ABSTRACT

Corbulid bivalves (Myacea: Corbulidae) are an important constituent of fossiliferous Neogene sediments of the Cibao Valley, northern Dominican Republic. Six corbulid species referred to five subgenera within the genus *Corbula* are described and figured (*Bothrocorbula*, *Caryocorbula*, *Juliacorbula*, *Panamicorbula*, and *Varicorbula*). One species is new, *Corbula* (*Panamicorbula*) *canae*. This is the first description of a fossil *Panamicorbula* species and the first description of a *Panamicorbula* species outside of the eastern Pacific. The distribution of Dominican corbulids is strongly influenced by paleoenvironmental conditions such as salinity, depth, and bioclastic fabric. Corbulids are most common in Miocene sediments that were deposited predominantly in shallow-marine waters. *Corbula* (*Caryocorbula*) *sericea* Dall, 1898 has the widest stratigraphic and geographic distribution within the study area and is especially abundant in brackish-water and very shallow-marine deposits. *Corbula* (*Bothrocorbula*) *viminea* Guppy, 1866b is also common in shallow-marine and brackish-water deposits. *Corbula* (*Varicorbula*) *sanctidominici* Maury, 1925 occurs predominantly in shallow-marine sediments, whereas *Corbula* (*Panamicorbula*) *canae* n. sp. is restricted to brackish-water deposits of the Upper Miocene Cercado Formation in the Río Cana section. *Corbula* (*Caryocorbula*) *dominicensis* Gabb, 1873b and *Corbula* (*Juliacorbula*) *fossilis* Pilsbry, 1922 are rare. *Corbula dominicensis* is apparently restricted to the upper Lower to lower Middle Miocene Baitoa Formation of the Río Yaque del Norte section, and *C. fossilis* is found in Upper Miocene sediments of the Cercado and Gurabo Formations. Dominican corbulid species show close morphologic affinities to species of the Pliocene Bowden Formation of Jamaica, Neogene units of the Caribbean coast of Central America such as the Gatun Formation and sediments of the Limón Basin, Miocene and Pliocene deposits of Trinidad, and Miocene to Pleistocene sediments of Florida.

RESUMEN

Los bivalvos corbúlidos (Myacea: Corbulidae) constituyen una parte importante de los sedimentos fosilíferos del Neógeno en el Valle de Cibao al norte de la República Dominicana. A continuación, se describe y se dibuja seis especies pertenecientes a cinco subgéneros dentro del género *Corbula*, es decir, *Bothrocorbula*, *Caryocorbula*, *Juliacorbula*, *Panamicorbula*, y *Varicorbula*. *Corbula* (*Panamicorbula*) *canae* forma una nueva especie. Por primera vez se describe la especie fósil *Panamicorbula* y es la primera vez que se describe la especie *Panamicorbula* fuera del Pacífico este. La distribución de corbúlidos dominicanos está influenciada fuertemente por condiciones paleoambientales tales como la salinidad, profundidad de agua y fábrica bioclástica. Los corbúlidos se encuentran más comúnmente en aquellos sedimentos del Mioceno depositados predominantemente en aguas marinas someras. Dentro de la zona de estudio, *Corbula* (*Caryocorbula*) *sericea* Dall, 1898 muestra tener la distribución estratigráfica y geográfica más amplia y abunda sobre todo en agua salobre y en depósitos marinos de agua muy someras. *Corbula* (*Bothrocorbula*) *viminea* Guppy, 1866b también se encuentra comúnmente en depósitos marinos de agua somera y en depósitos de agua salobre. *Corbula* (*Varicorbula*) *sanctidominici* Maury, 1925 aparece en sedimentos marinos de poca profundidad mientras que *Corbula* (*Panamicorbula*) *canae*, n. sp. se encuentra restringida a depósitos de agua salobre en la formación Cercado del Mioceno superior en la sección del Río Cana. *Corbula* (*Caryocorbula*) *dominicensis* Gabb, 1873b y *Corbula* (*Juliacorbula*) *fossilis* Pilsbry, 1922 son poco frecuentes. Aparentemente, *C. dominicensis* queda restringida entre la parte superior del Mioceno inferior y la parte inferior del Mioceno intermedio de la formación Baitoa en la sección del Río Yaque del Norte. *Corbula fossilis* se encuentra en los sedimentos de las formaciones Cercado y Gurabo con edad del Mioceno superior. Las especies de corbúlidos dominicanos muestran una afinidad morfológica a las especies de la formación Bowden del Plioceno en Jamaica, a las unidades Neógenas de la costa caribeña de centroamérica tales como la formación Gatun y los sedimentos de la cuenca Limón, a los depósitos de edad Miocena y Pliocena en Trinidad y a los sedimentos de Florida que comprenden desde el Mioceno hasta el Pleistoceno.

INTRODUCTION

This work is one of a series of taxonomic monographs on Neogene fossils of the Cibao Valley in the northern Dominican Republic (Text-fig. 1). Saunders *et al.* (1986) provide detailed information on measured sections and samples, and a general biostrati-

graphic framework. The units studied include the upper Lower to lower Middle Miocene Baitoa, Upper Miocene Cercado, Upper Miocene to Lower Pliocene Gurabo, and Lower Pliocene Mao Formations. Although not highly diverse, corbulid bivalves occur throughout the stratigraphic section. They are most abundant, however, in brackish-water and shallow-


marine sediments, which are typical of Miocene deposits in the study area.

ACKNOWLEDGMENTS


I am especially grateful for the generosity and assistance of Peter Jung, of the Naturhistorisches Museum Basel, Switzerland and Emily Vokes of Tulane University who provided long-term loans of extensive collections. A number of other institutions generously lent samples and specimens, and I would like to thank Warren Allmon of the Paleontological Research Institution; Thomas Waller, Warren Blow, and Jann Thompson of the United States National Museum of Natural History, Smithsonian Institution; Gary Rosenberg and Elana Benamy of the Academy of Natural Sciences of Philadelphia; Silvard Kool of the Museum of Comparative Zoology, Harvard University; Paul Taylor and Paul Jeffery of The Natural History Museum, London (British Museum, Natural History); and Klaus Westphal of the Museum of Geology, University of Wisconsin-Madison. Thanks also to Juan Lorenzo for translating the abstract, and to Emily Vokes, Jay Schneider, and John Kruger for reviewing the manuscript. This research was supported by the National Science Foundation (EAR-9316363), Sigma Xi, the Paleontological Society, and the Geological Society of America.

BIOSTRATIGRAPHY AND PALEOECOLOGY

Within the study area (Text-fig. 1), it is possible to trace changes in corbulid species distributions and intraspecific variability in a number of stratigraphic sections that record the interplay of paleoenvironment, time, and geography. Anderson (1994) documents in detail the relationship of corbulid species distributions and intraspecific variability to paleoenvironmental conditions in these sediments and those findings are reviewed here. Distributions of the most common species, *Corbula* (*Caryocorbula*) *sericea*, *Corbula* (*Bothrocorbula*) *viminea*, *Corbula* (*Varicorbula*) *sanctidominici*, and *Corbula* (*Panamicorbula*) *canae*, track paleoenvironmental conditions, and represent migrations into and out of the study area over time rather than speciation and extinction events (Anderson, 1994). Corbulid abundance and diversity reflect a preference for marginal-marine and shallow to intermediate marine habitats (< 100 m), which is compatible with habitat distributions of living corbulids. This correspondence of species distributions to paleoenvironmental conditions causes a temporal pattern in species distributions because paleoenvironmental conditions changed systematically through time in the study area (Saunders *et al.*, 1986). In the study area, corbulids are most abundant and diverse in Miocene marine sediments deposited primarily in shallow (approximately




Text-figure 1.—Index map of areas investigated in the Cibao Valley, Dominican Republic (after Saunders *et al.*, 1986).



Text-figure 2.—Part of the Río Cana section showing the stratigraphic distributions of *Corbula* species. Coral communities are based on average linkage cluster analysis of coral assemblages from Budd *et al.* (1996). Criteria used to distinguish environmental categories are outlined in Appendix 1.

0–30 m) to intermediate depths (approximately 30–100 m), whereas corbulids are much less common and diverse in Pliocene sediments deposited in deeper marine (> 100 m) waters (Text-figs. 2, 3; see Appendix 1 for criteria used to construct these paleoenvironmental categories).


Slight differences in environmental preferences exist among Dominican Republic corbulid species. *Corbula sericea* is most abundant in brackish-water and shallow-marine to intermediate-marine deposits, although it is conspicuously absent from sediments deposited in grass-flat habitats such as the lower part of the Gurabo



Text-figure 3.—Part of the Río Gurabo section showing the stratigraphic distributions of *Corbula* species. Coral communities are based on average linkage cluster analysis of coral assemblages from Budd *et al.* (1996). Criteria used to distinguish environmental categories are outlined in Appendix 1.

Formation in the Río Cana section (Text-fig. 2; Anderson, 1994). *Corbula viminea* also occurs in brackish-water and shallow-marine to intermediate-marine deposits in the study area, whereas *C. sanctidominici* occurs primarily in shallow- to intermediate-marine sedi-


ments (Text-figs. 2, 3). *Corbula canae* only occurs in brackish-water deposits of the Río Cana section, which were probably deposited in or near a mangrove swamp (Text-fig. 2; Anderson, 1994). *Corbula sericea* and *C. sanctidominici* also occur in deeper marine sediments



Text-figure 4.—Plot of first and second principle component scores (PC1 and PC2) of right valves of *Corbula sericea*. Procedures and results of the principal components analysis (PCA) are outlined in Anderson (1994). PC1 (explaining about 55 % of the variance) represents size and size-correlated shape variability. PC2 (explaining about 16 % of the variance) represents valve elongation, more elongate valves have negative principle component scores. Criteria used to distinguish environmental categories are outlined in Appendix 1. See Appendix 2 for samples used for each category.

(>100 m deep) that show evidence of downslope movement, such as the top of the Río Gurabo section (Text-fig. 3), the top of the Río Yaque del Norte section, and in the Cañada Zalaya section (Saunders *et al.*, 1986; Anderson, 1994).

Intraspecific variability in the two most abundant corbulid species, *C. sericea* and *C. viminea*, are also related to paleoenvironmental factors. *Corbula sericea* shows continuous morphologic variability along a paleoenvironmental gradient of salinity, depth, and bioclastic fabric (Text-fig. 4). The smallest and least elongate *C. sericea* valves are found in intermediate and deeper marine deposits. Intermediate morphologies occur in shallow-marine deposits, and larger (but not more elongate) valves generally occur in brackish-water deposits. A few valves categorized as "brackish-water" from the López section of the Río Yaque del Norte, however, do not fit this trend (triangles with negative values on the first principle component axis [$PC1 < 0$] in Text-fig. 4). This anomaly is caused by difficulties in assigning these sediments to an environmental category because of conflicting environmental interpretations based on different faunal components. Even though the ostracode and foraminiferal faunas of the López section indicate deposition in brackish wa-




Text-figure 5.—Plot of PC1 and PC2 of right valves of *Corbula sericea* from shallow-marine deposits of the Río Cana and Río Mao sections, where this species is locally abundant. Size and shape differences are related to differences in bioclastic fabric. This plot shows a subset of data illustrated in Text-figure 4. See Appendix 2 for samples used for each category. (After Anderson, 1994.)

ters (Saunders *et al.*, 1986; Bold, 1988), these sediments also are rich in irregular echinoids and massive reef corals (Saunders *et al.*, 1986) indicating a significant marine influence. Alternatively, the other brackish-water valves are from sediments with an unambiguous brackish-water signal. These sediments of the Río Cana section are rich in brackish-water mollusks, including beds of *Anadara patricia* (Sowerby, 1850) (= "Arca" beds of Saunders *et al.*, 1986). This species is closely related to or is a subspecies of *Anadara grandis* (Broderip and Sowerby, 1829), a Recent species inhabiting intertidal mud banks bordering mangrove swamps in the eastern Pacific (Maury, 1922; Olsson, 1932, 1961; Woodring, 1973; Saunders *et al.*, 1986).

Geographic variation related to bioclastic fabric also can be discerned within *C. sericea* from roughly contemporaneous Miocene sediments of the Río Cana and Río Mao sections (Text-fig. 5; Anderson, 1994). *Corbula sericea* is larger and more elongate in the Río Cana section, where it occurs mainly in silts with bioclasts concentrated in lenses. In the Río Mao section, *C. sericea* is smaller and less elongate, and occurs in lenticular beds rich in bioclasts with a silty matrix.

Variation in *C. viminea* shows a morphologic cline from west to east in contemporaneous sediments, with variability related to sediment type and bioclastic fabric (Text-fig. 6; Table 1; Anderson, 1994). *Corbula viminea* is relatively small in the west (Río Cana section, where it occurs in pebbly shell beds), whereas to the



Text-figure 6.—Plot of PC1 versus stratigraphic section (upper) and PC1 versus sediment type (lower) for *Corbula viminea*. Procedures and results of PCA are outlined in Anderson (1994). PC1 (explaining about 46 % of the variance) represents size and size-correlated shape variability. Sediment types are: 1 = silts with bioclasts concentrated into lenticular beds or lenses, 2 = silts with bioclasts concentrated into burrows, 3 = silts with bioclasts scattered, and 4 = silty sands with bioclasts either scattered or concentrated. Two valves from the Río Yaque del Norte section are not included in the lower plot due to a lack of information on sediment type. Note clinal variation from west to east (Río Cana to Río Mao section). Geographic variation is apparently related to differences in sediment type among sections (see Table 1). See Appendix 2 for samples used for each category. (After Anderson, 1994.)

east (Río Gurabo and Río Mao sections, where it occurs in lenticular-, burrow-, or lens-shaped shell concentrations within silts) it becomes progressively larger. Valves from the Río Yaque del Norte section are from older deposits of the Baitoa Formation and do not follow this trend. Morphological differences among the four sediment-type/bioclastic-fabric categories are significant using the nonparametric Kruskal-Wallis analysis of variance ($H=103$, $df=3$, $p < 0.005$).

In summary, both abundance of particular corbulid species within their stratigraphic ranges and total ranges within stratigraphic sections are controlled by paleoenvironmental factors. In addition, intraspecific morphologic variability in *C. sericea* and *C. viminea* corresponds strongly with specific paleoenvironmental conditions. Although aspects of intraspecific variability in both species are related to bioclastic fabric, taphonomic processes do not control the morphologic variability observed (Anderson, 1994). Morphologic

Table 1.—*Corbula viminea* valves from various sediment types for each stratigraphic section. Sediment type categories are based on descriptions in Saunders *et al.* (1986) and on personal observation. Categories are: 1) silts with bioclasts in lenticular beds or lenses, 2) silts with bioclasts filling burrows, 3) silts with mollusks dispersed in matrix, 4) silty sands with bioclasts dispersed or concentrated. Samples used are listed in Appendix 2.

section	sediment type			
	1	2	3	4
Cana	14	0	98	0
Gurabo	88	11	0	0
Mao	44	0	0	0
Yaque ¹	0	0	8	15

¹ Two valves from this section were not included in the analysis because sediment type was unknown.

change within these species over time is relatively minor or is a side effect of systematic changes in environmental conditions.

BIOGEOGRAPHY

In tropical America (including the Caribbean Sea, eastern Pacific Ocean, and western Atlantic Ocean), Miocene to Recent corbulid faunas are nearly identical at the subgenus level, except for a few apparently endemic, low-diversity taxa. Widespread and abundant subgenera include *Varicorbula* Grant and Gale, 1931 (*Notocorbula* Iredale, 1930 of some authors) and *Car-yocorbula* Gardner, 1926, and to a lesser extent *Both-rocorbula* Gabb, 1873a and *Juliacorbula* Olsson and Harbison, 1953. Endemic subgenera typically inhabit the Recent Panamic-Pacific province and include *Ser-racorbula* Olsson, 1961 and *Tenuicorbula* Olsson, 1932 (also found in the Tertiary of Peru, Venezuela, and Trinidad). *Panamicorbula* Pilsbry, 1932 was first described from the Recent Panamic-Pacific province, but also is reported from the Miocene of the Pacific coast of Costa Rica (Punta Judas; Seyfried *et al.*, 1985), the Miocene Cercado Formation of the Dominican Republic (Anderson, 1991, 1994), and the Pliocene l'Enfer and Springvale Formations of Trinidad (see p. 19).

Dominican corbulid species show affinities to a number of other Miocene to Pleistocene faunas. The Pliocene Bowden Formation of Jamaica shares two species with the Dominican fauna, *Corbula viminea* and *C. sericea*, and contains a species of *Varicorbula*, *Corbula* (*Varicorbula*) *heterogena* Guppy (in Dall, 1898), that is morphologically very similar to *C. sanctidominici*. *Corbula viminea* and *C. sericea* also are reported from Neogene deposits of the Limón Basin, Costa Rica (Dall, 1898; Olsson, 1922). In addition, the following units all contain a number of corbulid species with strong affinities to Dominican corbulids:

Miocene and Pliocene sediments of Trinidad (including the Manzanilla, Springvale, l'Enfer Formations; Maury, 1925; Jung, 1969), the Miocene Gatun Formation of Panama (Woodring, 1982), Upper Miocene Santa Rosa beds of Veracruz, Mexico (Perrilliat [1984], who assigns these beds to the Agueguexquite Formation; E. Vokes [1989] states, however, that this formation only occurs farther north, near Coatzacoalcos, and is Pliocene), and Miocene to Pleistocene sediments of Florida (Dall, 1898; Gardner, 1928; Olsson and Harbison, 1953).

ABBREVIATIONS OF REPOSITORY INSTITUTIONS

The following abbreviations for repository institutions are used in this paper:

- ANSP: Academy of Natural Sciences, Philadelphia, PA, U.S.A.
 IGM: Instituto de Geología, Ciudad Universitaria de México, D.F., México
 BMNH: The Natural History Museum, London, England, U.K. (British Museum, Natural History)
 NMB: Naturhistorisches Museum Basel, Switzerland
 PRI: Paleontological Research Institution, Ithaca, NY, U.S.A.
 TU: Tulane University, New Orleans, LA, U.S.A.
 USNM: United States National Museum of Natural History, Washington, DC, U.S.A.
 UW: Museum of Geology, University of Wisconsin-Madison, Madison, WI, U.S.A.

SYSTEMATIC PALEONTOLOGY

INTRODUCTION

All species described here are assigned to the genus *Corbula*; other supraspecific taxa are considered subgenera, following Vaught (1989). All subgenera share the same basic hinge structure and differ primarily in shape, ornamentation, and the degree of disparity in size, shape, and ornamentation of the left and right valves. A majority of species described here are abundant enough to incorporate intraspecific variation into interpretations of species boundaries (see also Anderson, 1991, 1994 for quantitative treatments). Variability is considered intraspecific if it can be related to size differences (presumably ontogenetic) and/or to changes in paleoenvironmental conditions. In comparison to this approach, the taxonomy of living corbulids has been more typological because taxonomic and systematic studies have not incorporated potential phenotypic variation caused by ontogenetic, environmental, or geographic factors.

Only forms considered identical to described species are listed in the synonymy. A question mark (?) before an item in a synonymy indicates that material was insufficient to confirm conspecific status. The abbreviation "sp." indicates that the described species could be identified to the subgenus but not to the specific level. *Diagnoses* are used both for species and for supraspecific categories and indicate the diagnostic features of a particular taxon. *Descriptions* are used for species only, and outline overall species morphology. The *Remarks* section provides information on the particular taxon described, and may include a taxonomic discussion, taphonomic and paleoenvironmental information, and geologic and geographic ranges (ranges for supraspecific taxa only). The *Comparisons* section outlines differences between the species being described and morphologically similar species. Detailed locality information for Dominican Republic samples is listed in the *Occurrence* section, whereas the *Distribution* section is a more general statement of a species' geographic and stratigraphic distribution inside and outside the Dominican Republic. A question mark (?) after a formation indicates that synonymy is uncertain.

SYSTEMATICS

Family CORBULIDAE Lamarck, 1818

Diagnosis.—Small- to moderate-sized sturdy shells (length typically 2 cm or less), inequilateral, and generally strongly inflated. Slightly to strongly inequivalved in size and shape; left valves smaller than right valves. Hinge simple with anterior cardinal tooth in right valve and socket in left valve. Resilifer present behind hinge; typically a projecting chondrophore in left valve that corresponds to socket-like resilifer in right valve. Pallial sinus small to obsolete. (See H. Vokes, 1945; Moore, 1969.)

Subfamily CORBULINAE Lamarck, 1818

Diagnosis.—Left valve typically slightly smaller than right valve. Chondrophore in left valve present in most species, fitting into socket-like resilifer in right valve. Posterior typically rostrate. (See H. Vokes, 1945; Moore, 1969.)

Genus CORBULA Bruguière, 1797

Corbula Bruguière, 1797, pl. 230.

Corbula Lamarck, 1799, p. 89.

Aloidis Megerle von Mühlfeldt, 1811, p. 67.

Type species.—*Corbula sulcata* Lamarck, 1801; by subsequent designation, Schmidt (1818); Recent, Senegal.

Diagnosis.—Shell sturdy, moderately inflated, ine-

quilateral and inequivalved; left valve smaller. Shells smooth to concentrically ribbed. Hinge with cardinal tooth in right valve and cardinal socket in left valve. In type species, socket-like resilifer present behind dentition in both valves; in most species, however, left valve with chondrophore and right valve with socket-like resilifer. (See H. Vokes, 1945.)

Remarks.—The generic name *Corbula* was first used in Bruguière (1797) in a plate title, and the name is generally credited to him, although he did not describe the genus. Lamarck (1799) first described *Corbula* but did not specify a type. Schmidt (1818) subsequently designated *Corbula sulcata* as type (see Stewart, 1930). *Aloidis* Megerle von Mühlfeldt (1811) is a synonym of *Corbula* (H. Vokes, 1945, 1980). Unlike most other members of the genus, the type species, *Corbula (Corbula) sulcata*, has no chondrophore in the left valve; the resilium instead is received in a socket-like resilifer behind the cardinal socket.

Geologic range of the genus is Cretaceous to Recent (Moore, 1969). The genus is found worldwide in tropical to temperate waters that range from marine to brackish salinities (Boss, 1982). Some species are tolerant of waters low in dissolved oxygen (Lewy and Samtleben, 1979).

Subgenus BOTHROCORBULA Gabb, 1873a

Bothrocorbula Gabb, 1873a, p. 274, pl. 10, figs. 3, 3a.

Type species.—*Corbula viminea* Guppy, 1866b; by monotypy. Pliocene, Bowden Formation, Jamaica.

Diagnosis.—Shell moderately large and thickened. Valves subequal, with coarse concentric ribs and fine radial striations. Characteristic deep lunular depression in front of umbos. Right valve hinge with cardinal tooth in front of socket-like resilifer. Left valve hinge with cardinal socket in front of chondrophore. (See Gabb, 1873a; Gardner, 1926; H. Vokes, 1945.)

Remarks.—This subgenus ranges from Miocene to Pleistocene in Florida, the West Indies, and eastern Central America (see p. 13–14). It is found in sediments deposited in shallow-marine and marginal-marine waters. The Miocene-to-Recent taxon *Hexacorbula* Olsson, 1932 closely resembles *Bothrocorbula* but lacks a lunular pit.

Corbula (Bothrocorbula) viminea Guppy, 1866b Plate 1, figures 1–8, 10, 11, 13, 14

Corbula viminea Guppy, 1866b, p. 293, pl. 18, fig. 11; Olsson, 1922, p. 270, pl. 28, fig. 25.

Corbula (Bothrocorbula) viminea Guppy. Maury, 1917, p. 233–234, pl. 39, figs. 20, 21; 1925, p. 108–109, pl. 19, fig. 19; Pillsbury, 1922, p. 428; Woodring, 1925, p. 189–190, pl. 26, figs. 5–8; Ramírez, 1950, p. 38–39, pl. 7, fig. 9; Anderson, 1994, figs. 2.1–2.4.

Diagnosis.—Species characterized by relatively large size, prominent lunule, thick valves, coarse concentric ribs, fine radial striations, evenly rounded anterior margin, and evenly rounded to slightly sinuous ventral margin.

Description.—Valves moderately large, subequal in size and shape. Right valve slightly larger than left, only overlapping left ventrally. Valve thickness widely variable, although variability in part preservational because valve inner layers tend to slough off. Valves elongate-ovate with rostrum and arcuate keel. On some valves, posterior slope has midline depression parallel to keel. Continuous variation seen in expression of rostrum and ventral margin, ranging from subdued rostrum and evenly rounded ventral margin, to short posteriorly-pointing rostrum and evenly rounded ventral margin, to short ventrally-pointing rostrum and gently sinuous ventral margin (concave just anterior of rostrum). Valve ornamented with coarse concentric ribs that die out before reaching keel. Fine concentric and radial striations superimposed on coarse ribs, and especially visible between ribs. Posterior slope and nematic shell with fine concentric striations, but lacking radial and coarse concentric ribs.

Both valves with deep lunule anterior of umbo. Lunule larger and deeper in left valve, encompassing entire hinge plate. Right valve hinge with large, triangular, hooked-shaped, cardinal tooth and posterior socket-like, broadly-open resilifer. Broad short ridge descends from resilifer roof and extends across part of hinge plate. Hinge plate surface depressed at resilifer. Left valve hinge with deep, triangular, hook-shaped anterior socket and broad posterior chondrophore. Hinge plate strongly sinuous resulting in obliquely-oriented cardinal socket. Dorsal surface of chondrophore with anterior and posterior ridges separated by midline trough. Posterior ridge more prominent and with denticle. Adductor muscle scars relatively large and thickened; posterior scar circular, anterior scar ovate. Pallial sinus obsolete.

Type Material.—Syntypes: BMNH 64088 (left valve), BMNH 64099 (right valve). Right valve figured by Guppy (1866b, Pl. 18, fig. 11) Both valves are figured here (Pl. 1, figs. 3, 6).

Type locality.—"Miocene" (= Bowden Formation, Pliocene), Jamaica. The type locality is here restricted to TU 705: type locality of Bowden Formation (Pliocene), Bowden, Parish of St. Thomas, Jamaica (fide H. Vokes, 1989).

Material.—Measured and/or figured specimens: NMB G 14103, 14104, 14105, 14106, 14107, 14108, 14109, 14110. Other specimens (over 600 valves) are cataloged by locality, which are listed in the Occurrence section.

Table 2.—Measurements of *Corbula* (*Bothrocorbula*) *viminea*. Figures are in mm.

	valve	length	height	width
BMNH 64088: syntype (Pl. 1, fig. 3)	right	19.1	13.9	6.3
BMNH 64099: syntype (Pl. 1, fig. 6)	left	15.1	10.3	5.0
USNM 115648: (figured by Woodring, 1925)	right	17.5	12.0	4.8
PRI 919: (figured by Maury, 1917)	left	14.0	9.6	4.1
PRI 919: (figured by Maury, 1917)	right	15.5	10.6	4.8
NMB G 14103: (Pl. 1, fig. 14); NMB locality 16923	left	15.9	11.8	4.9
NMB G 14104: (Pl. 1, fig. 13); NMB locality 16923	right	17.4	12.3	6.0
NMB G 14105: (Pl. 1, fig. 11); NMB locality 15900	left	15.3	11.3	5.4
NMB G 14106: (Pl. 1, fig. 10); NMB locality 15900	right	16.3	11.5	6.0
NMB G 14107: (Pl. 1, fig. 8); TU locality 1230	left	14.1	9.7	5.0
NMB G 14108: (Pl. 1, fig. 7); TU locality 1230	right	14.2	9.9	5.2
NMB G 14109: (Pl. 1, figs. 2, 5); TU locality 1364	left	13.3	9.3	3.8
NMB G 14110: (Pl. 1, figs. 1, 4); TU locality 1364	right	14.0	9.7	4.8

Remarks.—This is a common species in upper Miocene shallow-marine and brackish-water deposits of the Río Cana, Río Gurabo, Río Mao, Río Yaque del Norte, and Río Amina sections. It is typically found in silty shell beds or thin shell-rich stringers interbedded with silts. This species also is found in bioclast-rich sediment filling burrows, scattered in silts, and in pebbly and conglomeratic layers. Woodring (1925) states that Dominican forms of *C. viminea* are smaller and slightly more elongate than Jamaican forms.

Comparison.—*Corbula* (*Bothrocorbula*) *wilcoxii* Dall, 1898, a Pleistocene species from the Caloosahatchee and Bermont formations of southern Florida (Anderson, unpublished data), shows some morphologic overlap with *C. viminea*. *Corbula viminea* tends to be slightly larger and has a more evenly rounded anterior margin than *C. wilcoxii*. The valve margin of *C. wilcoxii* typically is flattened into a short horizontal ledge anterior of the beak, resulting in a projecting anterior. Although the two species typically are distinct, intermediate forms can be found in both species.

Corbula (*Bothrocorbula*) *synarmostes* Dall, 1898 of the Miocene Chipola Formation of Florida is smaller and has a much smaller lunule than *C. viminea*. *Corbula* (*Bothrocorbula*) *radiatula* Dall, 1898 of the Miocene Oak Grove Formation of Florida is also smaller

than *C. viminea*, has a reduced lunule, and more pronounced radial ornament.

Occurrence.—This species was collected from the following areas (see Saunders et al., 1986 for locality information):

Río Cana: Cercado Formation: TU 1230, and NMB 16835, 16836, 16837, 16838, 16839, 16844, 16857, 16988, 16989, 16993, 17005. Lower Gurabo Formation: NMB 16831, 16832, 16833, 16820. Upper Gurabo Formation: TU 1354, and NMB 16817–16819, 16824. Mao Formation (Mao Adentro Limestone Member): NMB 16873.

Río Gurabo: Cercado Formation: TU 1359, 1373, 1377, 1419, and NMB 15896, 15900, 15901, 15903, 15904, 15906, 15907, 15908, 15910. Lower Gurabo Formation: TU 1297, 1298, and NMB 15876, 15878, 15882, 15887.

Río Mao: Cercado Formation: TU 1294, and NMB 16913 (all correspond to Maury's Bluff 3); NMB 16915, 16917, 16918, 16923, 16924, 16926, 16927, 16928 (all Arroyo Bajón); NMB 16914, 16930, 16932 (all Maury's Bluff 2).

Río Amina: Gurabo Formation: TU 1412.

Río Yaque del Norte: Baitoa Formation: TU 1226, 1363, 1364, and NMB 16935, 16936, 16938, 17286, 17288, 17289 (all López section). Unnamed formation: TU 1445 (Angostura).

Distribution.—Upper Lower to lower Middle Miocene Baitoa, Upper Miocene Cercado, Upper Miocene to Lower Pliocene Gurabo, and Lower Pliocene Mao Formations, Dominican Republic; Miocene Thomonde and Las Canobas Formations (?), Haiti (see Guppy, 1876; Woodring et al., 1924; Woodring, 1925); Pliocene Bowden Formation, Jamaica; Pliocene Río Banano Formation, Costa Rica.

Subgenus **CARYOCORBULA** Gardner, 1926

Caryocorbula Gardner, 1926, p. 46.

Type species.—*Corbula alabamiensis* Lea, 1833, by original designation. Middle Eocene (Claibornian Stage) of Alabama.

Diagnosis.—Small- to moderately-sized, moderately thickened valves. Left valve slightly smaller than right. Shells typically elongate, with posterior keel and rostrum. Valves with moderately coarse concentric ribs; some also with fine radial striations. Right valve hinge with anterior cardinal tooth and posterior socket-like resilifer. Left valve hinge with anterior cardinal socket and posterior chondrophore. (See Gardner, 1926.)

Remarks.—*Caryocorbula* includes most American species assigned to *Cuneocorbula* Cossmann, 1886 by a number of authors (e.g., Dall, 1898; Maury, 1917).

Its geologic range is Eocene to Recent in North and South America and East Asia (Moore, 1969). *Caryocorbula* species inhabit shallow-marine to marginal-marine environments.

Corbula (Caryocorbula) dominicensis Gabb, 1873b

Plate 1, figures 9, 12; Plate 2, figures 1, 2, 4, 5

Corbula dominicensis Gabb, 1873b, p. 247; Pilsbry, 1922, p. 427, pl. 46, figs. 12, 13.

?*Corbula (Cuneocorbula) dominicensis* Gabb. Maury, 1917, p. 232, pl. 39, figs. 14, 15.

Diagnosis.—Species characterized by elongate shape and sculpture of concentric, closely-spaced, moderately coarse ribs and no radial striations. Also distinguished from other Dominican corbulids by relatively uninflated valves, moderately thickened shell, and large size.

Description.—Right and left valves subequal in size and shape; right valve slightly larger than left. Umbos slightly anterior of valve midline. Greatest convexity of ventral margin anterior of umbo in left valve but even with or anterior of umbo in right valve. Valves not strongly inflated and shells not greatly thickened. Sculpture consists of concentric, closely-spaced, flat-topped ribs with steep dorsal and more gradual ventral slopes. Ribs do not split and double towards posterior keel as described by Pilsbry (1922). Radial sculpture absent. Nepionic shell somewhat distinct, with very fine concentric ribs. Posterior region of valve with sharp arcuate keel and small rostrum. Left valve hinge with anterior, large, triangular socket that opens ventrally. Broad chondrophore posterior of cardinal socket, continuous with dorsal margin, and with midline cleft. Right valve hinge with anterior, large, hook-shaped, triangular cardinal tooth. Widely open socket-like resilifer present posterior of cardinal tooth. Long furrows for reception of left valve located anterior and posterior of, and continuous with, right valve hinge. Adductor muscle scars large and thickened; posterior scar circular, anterior scar ovate. Very small pallial sinus present.

Type Material.—Lectotype: ANSP 2691 (articulated shell). Specimens figured by Pilsbry (1922, p. 427, pl. 46, figs. 12, 13), who designated the lectotype, which is now lost (G. Rosenberg, pers. comm., 1993).

Type locality.—None designated. It is here designated as NMB 17281: Baitoa Formation (upper Lower to lower Middle Miocene), López section, Río Yaque del Norte, Dominican Republic.

Material.—Measured and/or figured specimens: NMB G 14111, 14112, 14113. Other specimens (four right valves, two left valves, three articulated shells, one internal mold, and two left valve fragments) are cataloged by locality, which are listed in the Occurrence section.

Table 3.—Measurements of *Corbula* (*Caryocorbula*) *dominicensis*. Figures are in mm.

specimen	valve	length	height	width
ANSP 2691: lectotype (figured by Pilsbry, 1922)	articulated	14.6	9.0	6.0 ¹
PRI 29033: (figured by Maury, 1917; refigured in Pl. 2, fig. 3)	left	13.4	8.6	3.3
PRI 29033: (figured by Maury, 1917; refigured in Pl. 2, fig. 6)	right	12.6	8.6	3.2
NMB G 14112: (Pl. 2, figs. 2, 5); TU locality 1226	left	13.6	8.2	3.1
NMB G 14113: (Pl. 2, figs. 1, 4); TU locality 1226	right	14.2	9.0	4.0
NMB G 14111: (Pl. 1, figs. 9, 12); NMB locality 17281	articulated	15.3	9.2	6.9 ¹

¹ diameter of articulated shell.

Measurements.—See Table 3.

Remarks.—This is a rare species found in conglomerates or conglomeratic lenses containing mollusks. In this study, it was found only in the upper Lower to lower Middle Miocene Baitoa Formation of the Río Yaque del Norte section (see Saunders *et al.*, 1986). Maury (1917), however, reports *C. dominicensis* from the upper Miocene Cercado Formation of the Río Cana Section (Zone H of the Río Cana at Caimito; equivalent to TU 1230 [Saunders *et al.*, 1986; H. Vokes, 1989]). Maury's specimens (refigured in Pl. 2, figs. 3, 5) differ from the Baitoa Formation specimens in several ways. Maury's specimens are smaller, less elongate, have a more centrally located umbo, more strongly arcuate keel, larger posterior slope, and coarser concentric ribs. Smaller specimens from the Baitoa Formation closely resemble Maury's specimens, but with the limited material available, it was not possible to unite or separate the specimens from the two formations.

Comparison.—*Corbula* (*Caryocorbula*) *democracia* F. Hodson, in Hodson and Hodson, 1931, from the Miocene of Falcón, Venezuela is much larger (holotype length is 22.5 mm), is less elongate, has a more convex ventral margin, and has coarser concentric ribs than *C. dominicensis*. *Corbula* (*Caryocorbula*) *prenasuta* Olsson, 1964 of the lower and middle Gatun Formation (Upper Miocene) of Panama and the Upper Miocene Angostura Formation of Ecuador is about the same size as *C. dominicensis* but is more strongly rostrate with the rostrum located in a more dorsal position on the posterior margin, and has a more strongly arcuate keel, giving the rostrum a twisted appearance. *Corbula* (*Caryocorbula*) *dominicensis veracruzana* Perrilliat, 1984 from the Upper Miocene Santa Rosa beds, Veracruz, Mexico more closely resembles *C. democracia* than *C. dominicensis* s. s., and probably is not a subspecies of *C. dominicensis*.

Occurrence.—This species was collected from the following areas (see Saunders *et al.*, 1986 for locality information):

Río Yaque del Norte: Baitoa Formation: TU 1226, and NMB 17281, 17283.

Distribution.—Upper Lower to lower Middle Miocene Baitoa, Upper Miocene Cercado (?) Formations, Dominican Republic.

Corbula (*Caryocorbula*) *sericea* Dall, 1898

Plate 2, figures 7–21

Corbula lavaleana Orbigny. Gabb, 1873b, p. 247; 1881, p. 371.

Corbula (*Corbula*) *sericea* Dall, 1898, p. 848–849; 1900, pl. 36, fig. 8; Woodring, 1925, p. 186–187, pl. 25, figs. 19–22.

Corbula (*Cuneocorbula*) *cercadica* Maury, 1917, p. 232–233, pl. 39, figs. 16, 17.

Corbula (*Cuneocorbula*) *caimitica* Maury, 1917, p. 233, pl. 39, figs. 18, 19.

Corbula sericea Dall. Pilsbry, 1922, p. 427.

Corbula (*Caryocorbula*) *cercadica* Maury. Anderson, 1994, figs. 1.1–1.5.

Diagnosis.—Species characterized by small, inflated, elongate-ovate to subtriangular valves with relatively fine, closely and evenly spaced concentric ribs, and very fine radial striations.

Description.—Shells small to moderately sized; moderately inflated. Valves thin to relatively thick, variability in part preservational. Left and right valves subequal in size and shape; right valve larger and slightly less elongate than left. Umbo at or slightly anterior of valve midline. Keel nearly straight to arcuate. Valve shape varies from triangular to elongate ovate; elongate valves more rostrate. Ornament of closely spaced concentric ribs. Fine radial ribs present but variably expressed. Radial striations present, beaded under magnification.

Right valve hinge with anterior, large, triangular, hook-shaped, cardinal tooth, and posterior, large, widely open, socket-like resilifer. Ridge bisects roof of resilifer, as in *C. viminea*. Long furrow present on either side of right valve hinge for reception of left valve's thickened dorsal margin. Posterior furrow continuous with resilifer. Left valve hinge with anterior, large, triangular, cardinal socket and broad posterior chondrophore. Anterior half of chondrophore's dorsal surface concave, posterior half convex. Small denticle present at posterior edge of chondrophore. Adductor muscle scars slightly thickened. Posterior scar circular; anterior scar ovate. Pallial sinus small to obsolete.

Type Material.—Lectotype: USNM 135655 (right valve). Lectotype designated by Woodring (1925). Specimen figured by Dall (1900, Pl. 36, fig. 8) and Woodring (1925, Pl. 25, figs. 19, 20), and refigured here (Pl. 2, fig. 7).

Type locality.—USGS locality 2692: track ballast

Table 4.—Measurements of *Corbula* (*Caryocorbula*) *sericea*.
Figures are in mm.

specimen	valve	length	height	width
USNM 135655: lectotype (Pl. 2, fig. 7)	right	5.3	4.0	2.0
PRI 29035 ¹ : (figured by Maury, 1917; refigured in Pl. 2, fig. 9)	left	5.6	3.9	2.0
PRI 29035 ¹ : (figured by Maury, 1917; refigured in Pl. 2, fig. 8)	right	6.6	4.6	2.3
NMB G 14114: (Pl. 2, fig. 17); NMB locality 16928	left	5.6	4.0	1.8
NMB G 14115: (Pl. 2, fig. 16); NMB locality 16928	right	6.1	4.5	2.1
NMB G 14116: (Pl. 2, fig. 19); NMB locality 15869	left	4.2	2.9	1.4
NMB G 14117: (Pl. 2, fig. 18); NMB locality 15869	right	4.9	3.2	1.6
NMB G 14118: (Pl. 2, figs. 11, 15); NMB locality 16848	left	7.5	4.7	2.4
NMB G 14119: (Pl. 2, figs. 10, 14); NMB locality 16848	right	7.0	5.0	3.0
NMB G 14120: (Pl. 2, fig. 13); NMB locality 16855	left	7.1	4.6	2.3
NMB G 14121: (Pl. 2, fig. 12); NMB locality 16855	right	8.1	4.8	2.7
NMB G 14122: (Pl. 2, fig. 21); TU locality 1227A	left	5.6	3.9	2.0
NMB G 14123: (Pl. 2, fig. 20); TU locality 1227A	right	6.0	4.2	2.3

¹ Misabeled as cotypes (syntypes) of *Corbula* (*Cuneocorbula*) *caimitica* but are *Corbula* (*Cuneocorbula*) *cercadica* illustrated in pl. 39, figs. 16, 17 of Maury 1917). The syntypes of *Corbula* (*Cuneocorbula*) *caimitica* are apparently lost (W. Allmon, pers. comm., 1994).

for railroad 1.5 miles west of Limón, Costa Rica. The source of the aggregate is USGS locality 2694: *in situ* Limón Reef (= Moín Formation, Pliocene).

Material.—Measured and/or figured specimens: NMB G 14114, 14115, 14116, 14117, 14118, 14119, 14120, 14121, 14122, 14123. Additional material: UW 1863/25, 1863/26. Other specimens (thousands of valves) are cataloged by locality, which are listed in the Occurrence section.

Measurements.—See Table 4.

Remarks.—This species is locally abundant in Upper Miocene shallow-marine (< 30 m) and brackish-water deposits of the Río Cana, Río Gurabo and Río Mao sections. It also occurs in Miocene and Pliocene intermediate and deeper marine (> 30 to + 100 m) sediments of the Río Cana, Río Gurabo, Cañada Zalaya, Río Amina, Río Verde, and Río Yaque del Norte sections. *Corbula sericea* is found in a variety of sediment types in the study area although it predominantly occurs scattered in silts and in shell beds with a silty matrix.

Corbula sericea is morphologically variable, although most shape variation is highly correlated with size. Size and size-correlated shape, in turn, are con-

tinuous and are closely related to paleoenvironmental conditions (Anderson, 1994). Specimens from very shallow marine deposits of the Río Mao have a sub-triangular valve outline (Pl. 2, figs. 16, 17). Average height to length ratio (H:L) is 0.72 (all height to length ratios for *C. sericea* reported here are based on data from Anderson, 1994). The ventral margin of these forms is directed upward at a slight angle in both directions from the midline. There is no invagination of the ventral margin in association with the keel or rostrum. The rostrum is very subdued to nearly absent and is directed downward. Most forms have an evenly rounded dorsal margin, although in some, the umbo is somewhat set off and projecting.

Specimens from very shallow marine sediments of the Río Cana section (Pl. 2, figs. 12, 13) tend to be larger and more elongate (average H:L = 0.63) than those of the Río Mao section. In addition, the rostrum in Río Cana specimens is located in a more dorsal position on the posterior margin, and it tends to point posteriorly rather than ventrally. As a result, valves have an ovate outline. Convexity of the keel varies, but most specimens have a slightly sinuous keel. The dorsoanterior slope is nearly straight, and the highest point of the valve is located more anteriorly than in the Río Mao specimens.

Brackish water forms from the Río Cana section (Pl. 2, figs. 10, 11, 14, 15) also are large, ovate, and elongate (average H:L = 0.68), although not as elongate as valves from very shallow-marine deposits of the Río Cana. In addition, the dorsoanterior slope is more rounded than in very shallow-marine forms. The rostrum is moderately expressed to obsolete, and when present, is directed ventrally. The ventral margin is strongly rounded, and the keel less sinuous than in shallow-marine forms of the Río Cana section.

Valves from intermediate and deeper marine deposits of the Río Gurabo, Río Mao, Río Cana, and Río Yaque del Norte sections tend to be smaller than those of other paleoenvironments but are very similar in shape to the Río Mao specimens. For these deeper water forms (Pl. 2, figs. 18, 19), H:L is 0.72 to 0.73 on average. Pliocene valves of deeper marine deposits of the Cañada Zalaya section (Pl. 2, figs. 20, 21) are similar in both size and shape to other deeper water forms, except that the ventral margin tends to be flatter.

Comparison.—Jung (1969) noted that small caryocorbulids of the Miocene and Pliocene of Trinidad were oversplit and considered *Corbula smithiana* Maury, 1912, and possibly *C. caribaea pergrata* Maury, 1925 and *C. daphnis* Maury, 1925, to be junior synonyms of *C. helenae* Maury, 1912. Although it is similar in shape to Río Cana morphologies of *C.*

sericea, *C. helenae* has a larger maximum size (up to 13 mm long), is more elongate, is less inflated, can be more coarsely sculptured, can have more prominent radial striations, and tends to have a more bulbous and projecting anterior. The species *C. manzanillensis* Maury, 1925 of the Miocene Manzanilla Formation of Trinidad is very small, has coarser ribs at comparable sizes, is strongly triangular, and less elongate than *C. sericea*.

Corbula (Caryocorbula) oropendula Olsson, 1922 has coarser sculpture, has a straighter keel and more ventrally located rostrum, is more elongate, and has a more strongly and evenly rounded ventral margin than *C. sericea*. *Corbula (Caryocorbula) oropendula dolicha* Woodring, 1982 is similar in shape to *C. oropendula* but has finer sculpture. *Corbula (Caryocorbula) oropendula stena* Woodring (1982) is much more rounded, tends to be smaller, and its rostrum creates a more prominent notch in the ventral margin than seen in *C. sericea*.

Occurrence.—This species was collected from the following areas (see Saunders *et al.*, 1986 for locality information):

Río Cana: Cercado Formation: TU 1230, and NMB 16838, 16839, 16841, 16843, 16844, 16845, 16846, 16848, 16850, 16851, 16853, 16854, 16855, 16856, 16986, 16987, 16988, 16989, 16990, 16993, 17001, 17003. Lower Gurabo Formation: NMB 16832. Upper Gurabo Formation: TU 1354, and NMB 16865, 17009.

Río Gurabo: Cercado Formation: TU 1277, 1419, and NMB 15900, 15904, 15910, 15911, 15912, 15925. Lower Gurabo Formation: TU 1211, 1215, 1278, and NMB 15842, 15846, 15854, 15860, 15863, 15864, 15869, 15871, 15873, 15882, 15936, 15937, 15941, 15944, 15945, 15947, 16808, 16809, 16810, 15836, 15835, 15952. Upper Gurabo Formation: TU 1210, and NMB 15933, 15935, 15939, 15964, 15966, 15969, 15805, 15804, 15814, 15815. Mao Formation: TU 1352, and NMB 15822, 15827, 15832, 15833.

Río Mao: Cercado Formation: TU 1294, and NMB 16912, 16913, 17269 (all correspond to Maury's Bluff 3 (1917)); NMB 16915, 16916, 16917, 16918, 16922, 16923, 16924, 16926, 16927, 16928 (all Arroyo Bajón); NMB 16914, 16929, 16930, 16931, 16932 (all Maury's Bluff 2); NMB 16802 (located between Bluff 1 and 2); TU 1293, and NMB 16910 (all Bluff 1), and TU 1225 (down stream and up section from Bluff 1).

Río Amina: Gurabo Formation: TU 1219, 1411, 1412.

Cañada Zalaya: Gurabo Formation: TU 1227, 1227A, 1453, 1453A.

Río Verde: Gurabo Formation: TU 1250.

Río Yaque del Norte: Baitoa Formation: TU 1226. Unnamed Formation: NMB 17273 (Arroyo López), NMB 17278 (Angostura). Gurabo Formation: TU 1403, 1405, 1448, 1449 (La Barranca), TU 1206 (Santiago).

Distribution.—Upper Lower to lower Middle Miocene Baitoa, Upper Miocene Cercado, Upper Miocene to Lower Pliocene Gurabo, and Lower Pliocene Mao Formations, Dominican Republic; Pliocene Bowden Formation, Jamaica; Pliocene Moín Formation, Costa Rica; Miocene Gatun Formation (?), Panama (see Brown and Pilsbry, 1911).

Subgenus JULIACORBULA

Olsson and Harbison, 1953

Juliacorbula Olsson and Harbison, 1953, p. 148–149.

Type species.—*Corbula aequivalvis* Philippi, 1836 (= *Corbula cubaniana* Orbigny, 1846; = *Corbula knoxiana* Adams, 1852b); by original designation. Recent, West Indies.

Diagnosis.—Shell small- to medium-sized, nearly equivalved. Subrectangular with strong keel and sharply truncated posterior. Well-defined escutcheon located behind beak. Hinge as in *Caryocorbula*. (See Olsson and Harbison, 1953; Olsson, 1961.)

Remarks.—*Juliacorbula* differs from *Caryocorbula* in shape and in the presence of an escutcheon. The type species was originally designated as *C. cubaniana*, which generally is agreed to be a junior synonym of *C. aequivalvis* (see McLean, 1951; Weisbord, 1964; Rios, 1975). The geologic range of *Juliacorbula* is Miocene to Recent in the West Indies, eastern Pacific, Central and South America, and Florida (Moore, 1969; Olsson and Harbison, 1953). Members of this group inhabit shallow-marine environments.

Corbula (Juliacorbula) fossilis Pilsbry, 1922

Plate 2, figures 22–26

Corbula contracta Say. Gabb, 1873b, p. 247.

Corbula knoxiana fossilis Pilsbry, 1922, p. 427, pl. 46, fig. 14.

?*Corbula (Cuneocorbula) cubaniana* Orbigny. Maury, 1925, p. 103–104, pl. 20, figs. 2–4.

?*Juliacorbula aequivalvis* (Philippi). Jung, 1969, p. 410–411, pl. 39, figs. 11–15.

Corbula (Juliacorbula) aequivalvis Philippi. Perrilliat, 1984, p. 17, pl. 16, figs. 1–4.

Diagnosis.—Species characterized by straight to slightly concave ventral margin, strongly angled posterior margin, strong keel and rostrum, and subtrapezoidal shape.

Description.—Valves relatively small, subtrapezoidal, and moderately inflated. Ventral margin flattened

to slightly concave at midline. Dorsoanterior margin also slightly concave in front of umbo. Directly posterior of beak, valve margin planar, gently sloping ventrally (sloping more steeply in left valves) to rostrum so that rostrum nearly as high as entire valve. Posterior of rostrum, valve margin nearly planar and vertical. Keel sharp and gently sinuous. Valve ornament of relatively coarse ribs with steep dorsal and gentle ventral slopes. Faint radial striations present on umbo.

Right valve hinge with moderately projecting, triangular, hook-shaped, cardinal tooth directly beneath beak. Posterior socket-like resilifer present beneath umbo. Hinge plate strongly sinuous, making resilifer nearly obsolete. Posterior of hinge, long L-shaped furrow present on right valve's posterior margin for reception of left valve. Left valve hinge with large, triangular, cardinal socket beneath beak and posterior broad chondrophore. Dorsal surface of chondrophore with anterior, midline and posterior ridges; small denticle present at end of posterior ridge. Adductor muscle scars large and moderately thickened; anterior scar ovate, posterior scar circular. Pallial sinus obsolete.

Type Material.—Holotype: ANSP 2689 (right valve). Figure by Pilsbry (1922, Pl. 46, fig. 14) and refigured here (Pl. 2, figs. 22, 23).

Type locality.—None designated. It is here designated as NMB 15914: Cercado Formation (Upper Miocene), Río Gurabo, Dominican Republic.

Material.—Measured and/or figured specimens: NMB G 14124, 14125.

Measurements.—See Table 5.

Remarks.—This rare species is found in shell-rich sediments with a silty matrix.

Comparison.—Species of *Juliacorbula* from the Tertiary of Trinidad (Maury, 1925; Jung, 1969) are

Table 5.—Measurements of *Corbula (Juliacorbula) fossilis*. Figures are in mm.

specimen	valve	length	height	width
ANSP 2689: holotype (Pl. 2, figs. 22, 23)	right	8.7	6.1	2.7
ANSP uncat.: paratype (Pl. 2, fig. 24)	left	8.4	5.8	2.8
ANSP uncat.: paratype	left	6.7	4.4	1.8
NMB G 14124: (Pl. 2, fig. 26); NMB locality 15914	right	5.7	4.1	1.6
NMB G 14125: (Pl. 2, fig. 25); NMB locality 16817	right	5.6	3.7	1.4
USNM 306431: (figured in Perrilliat, 1984); IGM locality 2851	left	8.7	6.8	2.2
PRI 870: (figured in Maury, 1925)	left	6.2	4.3	1.9
PRI 871: (figured in Maury, 1925)	right	7.4	5.1	2.3
PRI 872: (figured in Maury, 1925)	right	7.9	6.0	2.7

very similar to the Dominican species, although the posterior slope is nearly vertical in the Trinidad specimens and more oblique in Dominican forms. It is not possible at this time to determine whether this difference is of taxonomic significance because of the paucity of material. *Corbula (Juliacorbula) scutata* Gardner, 1943 of the Florida Pleistocene is very similar to *C. fossilis* but has coarser ribs, a more arched and less sinuous keel, a less concave dorsoanterior margin, and can be more elongate. The Pleistocene to Recent *C. aequivalvis* Philippi, 1836 (= *C. knoxiana* C. B. Adams, = *C. cubaniana* Orbigny) may be a peramorphic descendent of *C. fossilis*. Smaller specimens of *C. aequivalvis* overlap in morphology with *C. fossilis*. *Corbula aequivalvis* differs from *C. fossilis*, however in attaining a larger size, having a more rounded ventral margin that shows its greatest convexity anterior of the midline, not having a concave dorsoanterior margin, being more elongate, having a more sinuous keel, and tending to have finer ribs.

Occurrence.—This species was collected from the following areas (see Saunders et al., 1986 for locality information):

Río Cana: Upper Gurabo Formation: NMB 16817.

Río Gurabo: Cercado Formation: NMB 15914.

Distribution.—Upper Miocene Cercado, Upper Miocene to Lower Pliocene Gurabo Formations, Dominican Republic; Upper Miocene Santa Rosa beds, Veracruz, Mexico; Lower Pliocene Melajo Clay Member of the Springvale Formation(?), Pliocene Point Courbaril Sand and Clay Member of the l'Enfer Formation(?), Pliocene Matura Sand and Clay Member of the Talparo Formation(?), Trinidad.

Subgenus **PANAMICORBULA** Pilsbry, 1932

Panamicorbula Pilsbry, 1932, p. 105.

Type species.—*Potamomya inflata* Adams, 1852a (= *P. aequalis* Adams, 1852a, = *P. trigonalis* Adams, 1852a, = *Corbula macdonaldi* Dall, 1912); by original designation. Recent, Pacific Coast of Panama.

Diagnosis.—Valves moderately large and inflated but relatively thin, not rostrate. Surface smooth or with very fine concentric ribs. Hinge of right valve with anterior cardinal tooth and posterior socket-like resilifer. Left valve hinge with anterior cardinal socket and posterior chondrophore. (See Pilsbry, 1932; H. Vokes, 1945; Olsson, 1961.)

Remarks.—Contrary to the original description, no lateral teeth are present. What Pilsbry (1932) described as long laterals in the right valve are actually buttresses for grooves that receive the dorsal margin of the left valve (H. Vokes, 1945; Moore, 1969). Living *Panamicorbula* are found in the Panamic Province (eastern

Pacific; Mazatlán to Peru) in brackish water (Pilsbry, 1932; Olsson, 1961). The subgenus is reported as abundant but poorly preserved from Middle Miocene sediments at Punta Judas, Pacific Coast, Costa Rica (Seyfried et al., 1985). It is also present in USNM collections (with U.S. Geological Survey locality numbers) of the Lower Pliocene l'Enfer Formation (USGS 21842, USGS 20433) and Lower Pliocene Springvale Formation (USGS 20421, USGS 21083, USGS 20423) of Trinidad.

***Corbula (Panamicorbula) canae*, new species**
Plate 3, figures 1–10

Corbula (Panamicorbula) aff. C. inflata (C. B. Adams). Anderson, 1994, fig. 3.1.

Diagnosis.—Species characterized by roughly triangular shape, thin valves, fine concentric ribs, and left and right valves subequal in size and shape.

Description.—Valves relatively large (maximum length about 15 mm), inflated, and thin. Left and right valves subequal in size and shape; right valve slightly larger. Valve height shows positive allometry relative to valve length; larger valves more triangular, whereas smaller valves more quadrate. Ventral margin most convex anterior of midline, whereas umbo located at midline. Ventral margin of right valve rounded, of left valve slightly sinuous. Valve ornament of very fine, closely-spaced, concentric ribs. Radial ribs absent. Arcuate keel and subtle rostrum present. Right valve hinge with large, anterior, triangular, hook-shaped, cardinal tooth. Posterior, socket-like resilifer present beneath beak and opening ventrally. Elongate furrow present on both sides of right valve hinge for reception of left valve. Left valve hinge with large, anterior, triangular, cardinal socket and broad posterior chondrophore. Chondrophore continuous with valve margin and not strongly projecting. Low anterior, midline, and posterior ridges present on dorsal surface of chondrophore. Adductor muscle scars large but not thickened. Posterior scar circular; anterior scar ovate. Pallial sinus obsolete.

Etymology of name.—Name after Río Cana.

Type Material.—Holotype: NMB G 14126 (articulated shell). Figured in Plate 3, figures 1, 2.

Type locality.—NMB 16845: Cercado Formation (Upper Miocene), Río Cana, Dominican Republic. Paratypes are from NMB 16841, a nearby locality in the same lithologic unit.

Material.—Measured and/or figured specimens: NMB G 14126, 14127, 14128, 14129, 14130, 14131, 14132. Other specimens (11 articulated shells, 32 right valves, and 20 left valves) are cataloged by locality, which are listed in the Occurrence section.

Table 6.—Measurements of *Corbula (Panamicorbula) canae*. Figures are in mm.

specimen	valve	length	height	width
NMB G 14126: holotype (Pl. 3, figs. 1, 2); NMB locality 16845	articulated	14.4	11.8	9.6 ¹
NMB G 14127: paratype (Pl. 3, figs. 6, 7); NMB locality 16841	left	12.2	9.9	3.6
NMB G 14128: paratype (Pl. 3, fig. 8); NMB locality 16841	left	13.5	10.4	4.3
NMB G 14129: paratype (Pl. 3, fig. 5); NMB locality 16841	right	13.9	11.2	4.8
NMB G 14130: paratype (Pl. 3, figs. 3, 4); NMB locality 16841	right	12.4	10.2	3.4
NMB G 14131: (Pl. 3, fig. 9); NMB locality 16841	left	8.3	7.0	2.3
NMB G 14132: (Pl. 3, fig. 10); NMB locality 16841	right	7.1	5.5	1.5

¹ diameter of articulated shell.

Measurements.—See Table 6.

Remarks.—This is the first description of a fossil *Panamicorbula* species and the first description of a Caribbean *Panamicorbula*. This species is restricted to the “Arca” beds of the Upper Miocene Cercado Formation Río Cana section (see Saunders et al., 1986). It is found in interbedded shelly silts and silty clays, and in shell beds. Living representatives of *Panamicorbula* are restricted to the Pacific coast of Central America where they inhabit mangrove swamps and areas near the mouths of streams (Pilsbry, 1932; H. Vokes, 1945; Keen, 1971). *Corbula canae* apparently had similar environmental preferences because it occurs in sediments deposited in or near mangrove swamps (Anderson, 1994).

Comparison.—*Corbula (Panamicorbula) inflata* (Adams, 1852a) (synonyms: *C. aequalis* [Adams, 1852a], *C. trigonalis* [Adams, 1852a], and *C. macdonaldi* Dall, 1912) is much larger than *C. canae* and differs somewhat in shape. The ventral margin of *C. inflata* (Adams, 1852a) is flatter and is most convex near the valve midline, the keel is less arcuate, and the rostrum is absent.

Occurrence.—This species was collected from the following areas (see Saunders et al., 1986 for locality information):

Río Cana: Cercado Formation: NMB 16843, 16845, 16990, 16841, 16993, 16987, 16989, 16840, 16844, 16852, and 16842.

Distribution.—Upper Miocene Cercado Formation, Dominican Republic.

Corbula (Panamicorbula) sp.
Plate 3, figure 11

Diagnosis.—Small uninflated valves (< 6.5 mm) of *Panamicorbula* with rectangular shape.

Table 7.—Measurements of *Corbula* (*Panamicorbula*) sp. Figures are in mm.

specimen	valve	length	height	width
NMB G 14133: (Pl. 3, fig. 11); NMB locality 16990	right	5.4	4.0	1.3

Material.—Measured and/or figured specimens: NMB G 14113. Other specimens (15 right valves, and 4 left valves) are cataloged by locality, which are listed in the Occurrence section.

Measurements.—See Table 7.

Remarks.—These are small, apparently immature valves of a *Panamicorbula* species. Although these valves may be small individuals of *Corbula* (*Panamicorbula*) *canae*, the small number of valves for comparison and lack of intermediates makes assignment uncertain. These valves co-occur with *C. canae* in interbedded shelly silts and silty clays, and shell beds dominated by *Anadara patricia* in the upper part of the Upper Miocene Cercado Formation of the Río Cana section.

Comparison.—Valve shape of *Corbula* (*Panamicorbula*) sp. resembles *Caryocorbula*, but these valves are not as inflated as *Caryocorbula*, and the resilifer of the right valve opens ventrally (as in *Panamicorbula*). These valves differ from *Corbula* (*Panamicorbula*) *canae* in that they are small, much less inflated, and rectangular (rather than triangular) in shape.

Occurrence.—This species was collected from the following areas (see Saunders *et al.*, 1986 for locality information):

Río Cana: Cercado Formation: NMB 16845, 16990, 16993, 16987, 16989, 16846, 16852, 16986.

Distribution.—Upper Miocene Cercado Formation, Dominican Republic.

Subgenus **VARICORBULA** Grant and Gale, 1931

Varicorbula Grant and Gale, 1931, p. 420, footnote 1.

Type species.—*Tellina gibba* Olivi, 1792; by original designation. Recent, west coast of Europe and Mediterranean Sea.

Diagnosis.—Valves small to moderate in size with right and left valves strongly unequal in size, shape, and ornamentation. Right valve larger, more inflated and relatively higher; left valve smaller, more elongate, and much less inflated. Right valves with strongly expressed concentric ribs. Left valves with fine, widely spaced, radial ribs and fine concentric growth-lines; thicker concentric ribs may be present on beak and umbo. Right valve hinge with anterior cardinal tooth and posterior socket-like resilifer. Left valve hinge with anterior cardinal socket and posterior chondrophore.

Remarks.—Some workers (Stenzel *et al.*, 1957; Weisbord, 1964; Jung, 1969) consider *Varicorbula* to be a junior synonym of *Notocorbula* Iredale, 1930. Woodring (1982), however, advocated continued use of *Varicorbula* until the type species of *Notocorbula* was better known. Stenzel *et al.* (1957) state that the nepionic shells evident in both valves of the type species, *Corbula* (*Notocorbula*) *vicaria* (Iredale, 1930), can be seen in a more subdued form in *C. gibba* (Olivi, 1792), the type species of *Varicorbula*, and use this trait as a basis for synonymy. *Corbula vicaria*, however, does apparently differ from *C. gibba* in that left and right valves are subequal in size and shape, whereas *Varicorbula* is strongly inequivalved. Therefore, *Varicorbula* is used here.

The geologic range of *Varicorbula* is Eocene to Recent in eastern North America, Europe, and the eastern and western Pacific (Moore, 1969). *Varicorbula* species inhabit marine waters and can locally dominate the benthic fauna (e.g., Yonge, 1946).

***Corbula* (*Varicorbula*) *sanctidominici* Maury, 1925**
Plate 3, figures 12–18

Corbula disparilis Orbigny. Gabb, 1873b, p. 247.

Corbula vieta Guppy. Pilsbry, 1922, p. 427.

Corbula (*Aloidis*) *vieta* Guppy. Maury, 1917, p. 231–232, pl. 39, fig. 13.

Corbula (*Aloidis*) *sancti-dominici* Maury, 1925, p. 98–99, pl. 19, fig. 2.

Corbula (*Varicorbula*) *vieta* Guppy. Anderson, 1994, fig. 3.2.

Diagnosis.—Species characterized by highly inflated right valve with concave dorsoanterior slope, evenly rounded ventral margin, relatively narrow and anteriorly directed umbo, and near absence of rostrum and keel. Left valve characterized by quadrate shape and uninflated umbo.

Description.—Shells of moderate size. Valves strongly inequivalved in size, shape, and ornamentation. Right valve larger, greatly inflated, and subtriangular. Right valve also with very subtle to obsolete keel and rostrum, evenly spaced moderately coarse flat-topped concentric ribs, and evenly convex ventral margin. Valve shape varies with size. Small right valves inflated with concave dorsoanterior slope, umbo directed anteriorly, and obsolete keel. Inflation increases, dorsoanterior slope becomes less concave, and umbo becomes more dorsally oriented with increasing size. Subtle keel and slight rostrum also develop as size increases.

Left valves more elongate and quadrate, and much less inflated than right. Left valves with faint, concentric growth lines and widely spaced and slightly more distinct radial striations. Radial striations absent on posterior slope. Small left and right valves (2–3 mm

in length) very similar in shape, but radial ribs more prominent on left valves and concentric ribs more prominent on right valves. As size increases, left valves become more quadrate and keel become more strongly expressed.

Hinge of right valve with small, blunt, anterior cardinal tooth directly beneath beak and posterior, broad, socket-like resilifer that extends slightly beneath beak. Resilifer, appears reduced because hinge plate concave. Subsidiary denticle may occur above cardinal tooth, formed by projection of valve margin beneath beak. Furrows present on either side of right valve hinge for reception of left valve. Left valve hinge with an anterior small subtriangular socket, and posterior broad chondrophore. Dorsal surface of chondrophore with prominent anterior ridge, more subdued midline ridge, and posterior ridge with small denticle. Posterior portion of chondrophore projects strongly upward and may be visible externally. Muscle scars not thickened. Posterior scar circular; anterior scar ovate. Pallial sinus obsolete.

Type Material.—Holotype: PRI 903 (right valve). Figured by Maury (1917, Pl. 39, fig. 13; 1925, Pl. 19, fig. 2), and refigured here (Pl. 3, fig. 12).

Type locality.—Río Cana at Caimito, Dominican Republic (designated by Maury, 1925). The type locality is here restricted to TU 1230: Cercado Formation (Upper Miocene), Río Cana, Dominican Republic (fide Jung, 1986).

Material.—Measured and/or figured specimens: NMB G 14134, 14135, 14136, 14137. Other specimens (over 1,100) are cataloged by locality, which are listed in the Occurrence section.

Measurements.—See Table 8.

Remarks.—*Corbula sanctidominici* typically occurs scattered in silts and in bioclastic beds with a silty matrix. This species also occurs in bioclast-rich lenses and burrow-fills within silts.

The literature for Caribbean Neogene and Quaternary *Varicorbula* is complex. Of primary concern here are whether *Corbula* (*Varicorbula*) *sanctidominici* is a

junior synonym of 1) *C. vieta* Guppy, 1866a, a species originally described from the Miocene Manzanilla Formation of Trinidad, or 2) *C. operculata* Philippi, 1848 (= *C. disparilis* Orbigny, 1846?), a Recent Atlantic species. Gabb (1873b) placed *Varicorbula* from the Dominican Republic in *C. disparilis* and also considered *C. vieta* to be a junior synonym of *C. disparilis*. Recent specimens of *Varicorbula* of the western Atlantic represent a taxonomic quandary, and they have been variously assigned to *Corbula disparilis* Orbigny, 1846?; *C. operculata* Philippi, 1848; and *C. philippii* Smith, 1885 (see Weisbord, 1964 and Woodring, 1982 for discussion). The synonymy of these names is not controversial, although authors differ on which is senior. Woodring (1982) states that Orbigny's illustration is poor and the dates of publication controversial; the imprinted date is 1846, although the probable publication date is 1853 (Keen, 1971). Those who doubt the 1846 publication date use *C. operculata* Philippi, 1848 for this species. However named, the Recent species appears distinct from *C. vieta* s. s. and *C. sanctidominici*, because it attains a larger maximum size, is more elongate in shape with gentler anterior and posterior dorsal slopes, has coarser ribs, and has a stronger rostrum and keel.

Pilsbry (1922), in his revision of Gabb's Dominican species, concurs with Dall (1898) that *C. vieta* and *C. disparilis* are not synonymous, and assigned Gabb's specimens to *C. vieta*. Maury (1917) first placed her Dominican *Varicorbula* in *C. vieta*, but later (Maury, 1925) considered her Dominican form to be distinct, and named it *C. sanctidominici*. Maury (1925) stated that her Dominican specimen was larger (10 mm long, 10 mm high compared to 6 mm × 6 mm for *C. vieta* from the type area), more inflated, and had more numerous (about 26 rather than about 25) and more closely spaced ribs. Maury (1925), however, did not place Gabb's (1873b) Dominican *Varicorbula* specimens in synonymy with *C. sanctidominici*, stating they are either *C. vieta* or *C. sanctidominici*.

The type material of *C. vieta* (USNM 115650; left valves of *C. vieta* were assigned to *Erycina tensa* Guppy, 1866a, USNM 115652) are not well preserved, and the margins of the larger right valve are not complete, making comparison difficult. *Corbula vieta* from the type locality shows the same size range as Dominican varicorbulids, but tends to be more elongate, have a wider umbo, less concave dorsoanterior slope, and stronger keel.

The material from this study agrees well with Gabb's (1873b) material (ANSP 2690) from the Dominican Republic. Maury's type (PRI 903) of *C. sanctidominici* is, however, somewhat unusual for Dominican *Varicorbula*. Her specimen is a right valve that is

Table 8.—Measurements of *Corbula* (*Varicorbula*) *sanctidominici*. Figures are in mm.

specimen	valve	length	height	width
PRI 903: holotype (Pl. 3, fig. 12)	right	9.5	9.6	5.1
NMB G 14135: (Pl. 3, figs. 13, 18); NMB locality 16837	right	7.8	7.9	4.6
NMB G 14134: (Pl. 3, figs. 16, 17); NMB locality 16837	left	4.6	4.0	1.7
NMB G 14136: (Pl. 3, fig. 14); TU locality 1250	right	5.5	5.4	2.6
NMB G 14137: (Pl. 3, fig. 15); TU locality 1250	right	4.4	4.1	2.0

unusually large and coarsely ribbed. Unfortunately, the ventral margin is not intact so it is difficult to determine original valve shape, a diagnostic feature. Nevertheless, the traits that Maury noted as diagnostic for *C. sanctidominici* seem to be correlated with size in Dominican *Varicorbula*. Therefore, I place both my material and Gabb's Dominican material in *C. sanctidominici*.

Comparison.—*Corbula* (*Varicorbula*) *sanctianderaea* Maury (1925) of the Miocene Manzanilla Formation of Trinidad has a left valve with a very convex beak that is subequal in size to the right valve's beak. In addition, the right valve of *C. sanctianderaea* is relatively more elongate and subequilateral with a wider umbo and stronger rostrum than *C. sanctidominici*.

Corbula heterogena Guppy (in Dall, 1898) of the Pliocene Bowden Formation of Jamaica is very similar in size and shape to *C. sanctidominici*. In *C. heterogena*, however, the umbos of the right valve are less elevated and prominent, and are not as strongly directed anteriorly because the dorsoanterior margin is less concave. Therefore, in *C. sanctidominici* the right valve umbo appears narrower and more set off from the ventral portion of the valve. In addition, the right valve of *C. heterogena* is more elongate and has a stronger rostrum and keel. The left valves of *C. heterogena* are more inflated and have more prominent beaks.

Woodring (1982) assigns specimens of the Miocene and Pliocene of Panama and Costa Rica to *Corbula* (*Varicorbula*) *disparilis*. He also considered *C. waltonensis* Gardner, 1928 from the Miocene of Florida a junior synonym of *C. disparilis*, thus allowing much morphologic variation in the species. Woodring's (1982) figured specimens are very similar to *C. heterogena*. These Central American forms differ from *C.*

sanctidominici in having a stronger rostrum and keel, beaks directed dorsally rather than anteriorly, and a somewhat sinuous rather than straight ventral margin.

Occurrence.—This species was collected from the following areas (see Saunders *et al.*, 1986 for locality information):

Río Cana: Cercado Formation: TU 1230, and NMB 16835, 16838, 16837, 16842, 16857, 17005. Lower Gurabo Formation: NMB 16828, 16832, 16833, 16834. Upper Gurabo Formation: TU 1354, and NMB 16817, 16818, 16959, 16824.

Arroyo Ballaco: Cercado Formation: TU 1420.

Río Gurabo: Cercado Formation: NMB 15895, 15896, 15906, 15900. Lower Gurabo Formation: TU 1215, 1277, 1211, and NMB 15846, 15860, 15863, 15864, 16810, 15869, 15871, 15873, 15874, 15878, 15882, 15836, 15944, 15952, 15954. Upper Gurabo Formation: TU 1210, and NMB 15804, 15805.

Río Mao: Cercado Formation: NMB 16927, 16915, 16926, 16924 (all correspond to Arroyo Bajón); NMB 16929, 16914 (all Maury's Bluff 2); TU 1410, and NMB 16802 (between Maury's Bluff 1 and 2); TU 1293, NMB 16910 (Maury's Bluff 1); TU 1225 (downstream of Maury's Bluff 1).

Cañada Zalaya: Gurabo Formation: TU 1227, 1227a, 1453, 1453a.

Río Yaque del Norte: Baitoa Formation: TU 1363, and NMB 16938 (all López section). Unnamed Formation: NMB 17273 (Arroyo López). Gurabo Formation: TU 1449, 1448, 1405, 1403 (La Barranca); TU 1206 (Santiago).

Río Verde: Gurabo Formation: TU 1250.

Distribution.—Upper Lower to lower Middle Miocene Baitoa, Upper Miocene Cercado, Upper Miocene to Lower Pliocene Gurabo Formations, Dominican Republic.

REFERENCES CITED

Adams, C. B.

- 1852a. Catalogue of shells collected at Panama, with notes on their synonymy, station, and geographical distribution. Lyceum of Natural History of New York, Annals, vol. 5, pp. 1-334.

- 1852b. Descriptions of new species of *Corbula* from Jamaica. Contributions to Conchology, vol. 12, pp. 233-241.

Anderson, L. C.

1991. Neogene corbulid bivalves of the Dominican Republic and Florida: Species distributions, intraspecific variability, and patterns of naticid gastropod predation. Unpublished PhD Thesis, University of Wisconsin-Madison, 174 pp.

1994. Paleoenvironmental control of species distributions and intraspecific variability in Neogene Corbulidae (Bivalvia: Myacea) of the Dominican Republic. Journal of Paleontology, vol. 68, pp. 460-473.

Bold, W. A. van den

1988. Neogene paleontology in the northern Dominican Republic. 7. The subclass Ostracoda (Arthropoda: Crustacea). Bulletins of American Paleontology, vol. 94, pp. 1-105, pls. 1-13.

Boss, K.

1982. Mollusca. in: Synopsis and Classification of Living Organisms. S. Parker, ed., McGraw-Hill, New York, vol. 1, pp. 945-1169.

Broderip, W. J., and Sowerby, G. B.

1829. Observations on new or interesting Mollusca contained, for the most part, in the Museum of the Zoological Society. Zoological Journal, London, vol. 4, pp. 359-379, pl. 9.

Brown, A. P., and Pilsbry, H. A.

1911. Fauna of the Gatun Formation, Isthmus of Panama. Academy of Natural Sciences of Philadelphia, Proceedings, vol. 63, pp. 336-373, pls. 22-29.

Bruguère, J. G.

1797. Tableau encyclopédique et méthodique des trois règnes de la nature; vers testacées à coquilles bivalves. Paris, vol. 1, 85-132, pls. 96-286.

Budd, A. F., Johnson, K. G., and Stemmann, T. A.

1996. Plio-Pleistocene turnover in the Caribbean reef coral fauna. in Environment and evolution in Tropical America. J.B.C. Jackson, A.G. Coates, and A.F. Budd, eds.. University of Chicago Press, Chicago, Illinois (in press).

Cossmann, M.

1886. Catalogue illustré des coquilles fossiles de l'Eocene des environs de Paris. Société Royale Malacologique de Belgique, Annales, vol. 21, p. 46.

Dall, W. H.

- 1890-1903. Contributions to the Tertiary fauna of Florida with especial reference to the Silex beds of Tampa and the Pliocene beds of the Caloosahatchie River, including in many cases a complete revision of the generic groups treated of and their American Tertiary species. Wagner Free Institute of Science of Philadelphia, Transactions, vol. 3, 1654 pp., 60 pls. [Part 1, pp. 1-200, pls. 1-12, 1890; Part 2, pp. 201-473, pls. 13-22, 1892; Part 3, pp. 483-570, 1875; Part 4, pp. 571-947, pls. 23-35, 1898; Part 5, pp. 949-1218, pls. 36-47, 1900; Part 6, pp. 1219-1654, pls. 46-60, 1903.]
1912. New species of fossil shells from Panama and Costa Rica collected by D. F. MacDonald. Smithsonian Miscellaneous Collections, vol. 59, pp. 1-10.

Gabb, W. M.

- 1873a. Description of some new genera of Mollusca. Academy of Natural Sciences of Philadelphia, Proceedings, vol. 24 (for 1872), pp. 270-274, pls. 9-11.
- 1873b. On the topography and geology of Santo Domingo. American Philosophical Society, Transactions, series 2, vol. 15, pp. 49-259.
1881. Descriptions of new species of fossils from the Pliocene Clay Beds between Limón and Moen, Costa Rica, together with notes on previously known species from there and elsewhere in the Caribbean area. Academy of Natural Sciences of Philadelphia, Journal, series 2, vol. 8, pp. 349-380, pls. 45-47.

Gardner, J. A.

1926. The nomenclature of the superspecific groups of *Corbula* in the lower Miocene of Florida. The Nautilus, vol. 40, pp. 41-47.
1928. The molluscan fauna of the Alum Bluff Group of Florida. Part V. Tellinacea, Solenacea, Mactracea, Myacea, Molluscoidea. United States Geological Survey, Professional Paper, vol. 142-E, pp. 185-240, pls. 29-36.
1943. Mollusca from the Miocene and Lower Pliocene of Virginia and North Carolina. Part I. Pelecypoda. With a summary of the stratigraphy by W. C. Mansfield. United States Geological Survey, Professional Paper, vol. 199-A, pp. 1-178, pls. 1-23.

Grant, U. S., IV, and Gale, H. R.

1931. Catalogue of the marine Pliocene and Pleistocene Mollusca of California and adjacent regions with notes on their morphology, classification, and nomenclature and a special treatment of the Pectinidae and Turridae (including a few Miocene and Recent species) together with a summary of the stratigraphic relations of the formations involved. San Diego Society of Natural History, Memoirs, vol. 1, pp. 1-1036, pls. 1-32.

Guppy, R. J. L.

- 1866a. On the relations of the Tertiary formations of the West Indies with a note on a new species of *Ranina*, by Henry Woodward, Esq., F. G. S.; and on the Orbitoides and Nummulinae, by Prof. T. Rupert Jones, F. G. S. Geological Society of London, Quarterly Journal, vol. 22, pp. 570-590, pl. 26.
- 1866b. On the Tertiary Mollusca of Jamaica. Geological Society of London, Quarterly Journal, vol. 22, pp. 281-295, pls. 16-18.
1876. On the Miocene fossils of Haiti. Geological Society of London, Quarterly Journal, vol. 32, pp. 516-532, pls. 28, 29.

Hodson, F., and Hodson, H. K.

1931. Some Venezuelan mollusks. Bulletins of American Paleontology, vol. 16, pp. 1-94, pls. 1-24.

Iredale, T.

1930. More notes on the marine Mollusca of New South Wales. Records of the Australian Museum, vol. 17, pp. 384-407, pls. 62-65.

Jung, P.

1969. Miocene and Pliocene mollusks from Trinidad. Bulletins of American Paleontology, vol. 55, pp. 289-657, pls. 13-60.
1986. Neogene paleontology in the northern Dominican Republic. 2. The genus *Strombina* (Gastropoda: Columbellidae). Bulletins of American Paleontology, vol. 90, pp. 5-42, pls. 1-14.

Keen, A. M.

1971. Sea shells of tropical Western America. Stanford University Press, Stanford, California (Second Edition), 1064 pp.

Lamarck, J. B. P.

1799. Prodrome d'une nouvelle classification des coquilles. Mémoire Société Histoire Naturelle, Paris, pp. 69-91.
1801. Système des animaux sans vertèbres, ou tableau général des classes, des ordres et des genres de ces animaux. Paris, 432 pp.
1818. Histoire naturelle des animaux sans vertèbres. Paris, vol. 5, 1-612 pp.

Lea, I.

1833. Contributions to geology (Tertiary formation of Alabama; New Tertiary fossil shells from Maryland and New Jersey; New genus of fossil shell from New Jersey; Tuffaceous lacustrine formation of Syracuse, Onondaga Co., N.Y.). Philadelphia, 227 pp.

Lewy, Z., and Samtleben, C.

1979. Functional morphology and palaeontological significance of the conchiolin layers in corbulid pelecypods. Lethaia, vol. 12, pp. 341-351.

Maury, C. J.

1912. A contribution to the paleontology of Trinidad. Academy of Natural Sciences of Philadelphia, Journal, series 2, vol. 15, pp. 23-112, pls. 5-13.
1917. Santo Domingo type sections and fossils. Part 1: Mollusca. Bulletins of American Paleontology, vol. 5, pp. 1-251, pls. 1-39.
1922. The Recent Arcas of the Panamic Province. Palaeontographica Americana, vol. 1, pp. 163-208, pls. 1-3.
1925. A further contribution to the paleontology of Trinidad (Miocene horizons). Bulletins of American Paleontology, vol. 10, pp. 153-402, pls. 12-54.

McLean, R. A.

1951. The Pelecypoda or bivalve mollusks of Porto Rico and the Virgin Islands. Scientific Survey of Puerto Rico and

- the Virgin Islands, The New York Academy of Sciences, vol. 17, part 1, pp. 1-177, pls. 1-26.
- Megerle von Mühlfeldt, J. C.**
1811. Entwicklung eines neuen System der Schalthiergehäuse. Berlin, Gesellschaft von Naturforscher Freunde Magazin, vol. 5, pp. 38-72.
- Moore, R. C., editor.**
1969. Treatise on Invertebrate Paleontology. Part N. Mollusca 6. Bivalvia. The Geological Society of America, and The University of Kansas, Boulder, Colorado, vol. 2, pp. 491-952.
- Olivi, G.**
1792. Zoologia Adriatica ossia catalogo ragionato degli animali del Golfo e delle Lagune di Venezia. Bassano, 334 pp., 9 pls.
- Olsson, A. A.**
1922. The Miocene of northern Costa Rica with notes on its general stratigraphic relations. Bulletins of American Paleontology, vol. 9, pp. 1-168, pls. 1-32.
1932. Contributions to the Tertiary paleontology of northern Peru: Part 5, The Peruvian Miocene. Bulletins of American Paleontology, vol. 19, pp. 1-272, pls. 1-24.
1961. Mollusks of the tropical eastern Pacific particularly from the southern half of the Panamic-Pacific faunal province (Panama to Peru): Panama-Pacific Pelecypoda. Paleontological Research Institution, Ithaca, New York, 574 pp., 86 pls.
1964. Neogene mollusks from northwestern Ecuador. Paleontological Research Institution, Ithaca, New York, 256 pp., 38 pls.
- Olsson, A. A., and Harbison, A.**
1953. Pliocene Mollusca of southern Florida with special reference to those from North Saint Petersburg, with special chapters on Turridae by William G. Fargo, and Vitrinellidae and fresh-water mollusks by Henry A. Pilsbry. Academy of Natural Sciences of Philadelphia, Monographs, vol. 8, pp. 1-458, pls. 1-65.
- Orbigny, A. d'**
1841-1846. Mollusques. in: Histoire physique, politique, et naturelle de l'île de Cuba, by R. de la Sagra. A. Bertrand, Paris. (Two volumes and atlas issued as of 1853 but published in parts earlier) French ed., 1841-52: v. 1, p. 1-208 (1841), pp. 209-264, (1842), v. 2, pp. 1-112 (1842), pp. 113-380 (imprinted date 1846 but probably 1853); Atlas, pls. 1-28 (1842). Spanish ed. (1845).
- Perrilliat, M. del C.**
1984. Monografía de los moluscos del Mioceno medio de Santa Rosa, Veracruz; Parte VII. (Pelecípodos: Dreissenidae a Verticordiidae). Universidad Nacional Autónoma de México, Instituto Geología, Paleontología Mexicana, no. 48, pp. 1-88, pls. 1-25.
- Philippi, R. A.**
1836. Beschreibung einiger neuen Conchylien-Arten (*Vermetus spiratus*, *Diplodonta semiaspera*, *Tellina sulcata*, *Corbula aequivalvis*, *Chama cancellata*) und Bemerkungen über die Gattung *Lacuna*, Turton. Archiv für Naturgesellschaft, vol. 2, pp. 337-368.
1848. Beschreibung zweier neuer Conchylien aus der Sammlung des Herrn Consul Gruner in Bremen. Zeitschrift für Malakozoologie, vol. 5, pp. 13-27.
- Pilsbry, H. A.**
1922. Revision of W. M. Gabb's Tertiary Mollusca of Santo Domingo. Academy of Natural Sciences of Philadelphia, Proceedings, vol. 73, pp. 305-435, pls. 16-47.
1932. Notes on a Panamic corbulid clam. The Nautilus, vol. 45, p. 105.
- Ramírez, R.**
1950. Descripción de algunos moluscos del Mioceno del Valle del Cibao de la República Dominicana. Publicaciones de la Universidad de Santo Domingo, series 4, vol. 1, pp. 3-39, pls. 1-7.
- Rios, E. de C.**
1975. Brazilian marine mollusks iconography. Museu Oceanográfico, Río Grande-RS, XII, Brazil, 331 pp., 91 pls.
- Saunders, J. B., Jung, P., and Bijou-Duval, B.**
1986. Neogene paleontology in the northern Dominican Republic. 1. Field surveys, lithology, environment, and age. Bulletins of American Paleontology, vol. 89, pp. 1-79, pls. 1-9.
- Schmidt, F. C.**
1818. Versuch über die beste Einrichtung zur Aufstellung, Behandlung und Aufbewahrung der verschiedenen Naturkörper und Gegenstände der Kunst, vorzüglich der Conchylien-Sammlungen, nebst kurzer Beurtheilung der conchyliologischen Systeme und Schriften und einer tabellarischen Zusammenstellung und Vergleichung der sechs besten und neuesten conchyliologischen Systeme, welchen ein Verzeichniss der am meisten bekannten Conchylien angehängt ist, wie solche nach dem Lamarkischen System geordnet werden können. Gotha. Justus Perthes, pp. 77, 177.
- Seyfried, H., Sprechmann, P., and Aguilar, T.**
1985. Sedimentología y paleoecología de un estuario del litoral Pacífico del Istmo Centroamericano primordial (Mioceno Medio, Costa Rica). Revista Geológica de América Central, vol. 3, pp. 1-68.
- Smith, E. A.**
1885. Lamellibranchiata, Report on the scientific results of the voyage of H.M.S. Challenger during the years 1873-1876. Zoology, vol. 13, pp. 1-341, pls. 1-25.
- Sowerby, G. B.**
1850. in Moore, J. C., Descriptions of new species of fossil shells found by J. S. Heniker, Esq. Geological Society of London, Quarterly Journal, vol. 6, pp. 44-53, pls. 9, 10.
- Stenzel, H. B., Krause, E. K., and Twining, J. T.**
1957. Pelecypoda from the type locality of the Stone City Beds (Middle Eocene) of Texas. Bureau of Economic Geology, The University of Texas at Austin, publication 5704, Austin, Texas, 237 pp., 22 pls.
- Stewart, R. B.**
1930. Gabb's California Cretaceous and Tertiary type lamellibranchs. Academy of Natural Sciences of Philadelphia, Special Publication, No. 3, 314 pp., 17 pls.
- Vaught, K. C.**
1989. A classification of the living Mollusca. American Malacologists, Inc., Melbourne, Florida, 195 pp.
- Vokes, E. H.**
1989. Neogene paleontology in the northern Dominican Republic. 8. The Family Muricidae (Mollusca: Gastropoda). Bulletins of American Paleontology, vol. 97, pp. 5-94, pls. 1-12.
- Vokes, H. E.**
1945. Supraspecific groups of the pelecypod family Corbulidae. American Museum of Natural History, Bulletin, vol. 86, pp. 5-32, pls. 1-4.
1980. Genera of the Bivalvia: A Systematic and Bibliographic Catalogue (Revised and Updated). Paleontological Research Institution, Ithaca, New York, 307 pp.

1989. Neogene paleontology in the northern Dominican Republic. 9. The Family Cardiidae (Mollusca: Bivalvia). *Bulletins of American Paleontology*, vol. 97, pp. 95-130, pls. 13-19.
- Weisbord, N. E.**
1964. Late Cenozoic pelecypods from northern Venezuela. *Bulletins of American Paleontology*, vol. 45, pp. 1-564, pls. 1-59.
- Woodring, W. P.**
1925. Miocene mollusks from Bowden, Jamaica; part 1, pelecypods and scaphopods. Carnegie Institution of Washington, publication No. 366, pp. i-vii, 1-222, pls. 1-28.
1973. Geology and paleontology of Canal Zone and adjoining parts of Panama. Description of Tertiary mollusks (additions to gastropods, scaphopods, pelecypods: Nuculidae to Malleidae). United States Geological Survey, Professional Paper 306-E, pp. 453-539, pls. 67-82.
1982. Geology and paleontology of Canal Zone and adjoining parts of Panama. Description of Tertiary mollusks (Pelecypods: Propeamussiidea to Cuspidariidae; additions to families covered in P 306-E; Additions to gastropods; cephalopods). United States Geological Survey, Professional Paper, vol. 306-F, pp. 541-759, pls. 83-124.
- Woodring, W. P., Brown, J. S., and Burbank, W. S.**
1924. Geology of the Republic of Haiti. Republic of Haiti Geological Survey, 631 pp., 40 pls.
- Yonge, C. M.**
1946. On the habits and adaptations of *Aloidis* (*Corbula*) *gibba*. *Journal of the Marine Biological Association of the U.K.*, vol. 26, pp. 358-376.

APPENDIX 1

Criteria used to distinguish four environmental categories, based on the paleoenvironmental interpretations of Saunders *et al.* (1986) and Bold (1988) primarily using macrofossil and microfossil assemblages.

- Brackish:** Characterized by mollusks such as *Larkinia*, *Mytilus*, and *Melongena*, *Anadara patricia*, and brackish-water ostracodes.
- Shallow:** Depths approximately 0–30 m. Characterized by shallow-marine benthic foraminifera (*Amphistegina*, soritids, miliolids), shallow-marine mollusks (*Pachycrommium*, *Stigmaulux*, *Anadara*, *Tellina*, *Strombina*) and shallow-marine ostracodes (*Cytherella*, *Radimella*, *Caudites*, *Proteoconcha*, *Loxoconcha*, *Paracytheridea*). Planktonic foraminifera and calcareous nanofossils are absent.
- Intermediate:** Depths approximately 30–100 m. Characterized by abundant and diverse assemblage of shallow-water ostracodes, benthic foraminifera, corals, mollusks (including *Strombus*, *Oliva*, *Polystira*, and *Lyria*), and a few planktonic foraminiferal species.
- Deep:** Depths > 100 m. Characterized by rich assemblage of planktonic foraminifera, high ratios of planktonic to benthic foraminifera, deep water ostracodes (e.g., *Krithe*), and pteropods.

APPENDIX 2

Samples used for analyses illustrated in Text-figures 4–6. Samples selected to provide broad stratigraphic coverage. Abbreviations are as follows:

Section = Stratigraphic section; Cana = Río Cana; Gurabo = Río Gurabo; Mao = Río Mao; Yaque = Río Yaque del Norte; Zalaya = Cañada Zalaya.

Formation = Geologic Formation. If blank, Saunders *et al.* (1986) did not assign.

Age = Geologic age.

Environment = Environmental category (for *Corbula sericea*). See Appendix 1 for criteria used to distinguish categories.

Sed. Type = Sediment type (for *Corbula viminea*). Categories are: 1 = silts with bioclasts in lenticular beds or lenses; 2 = silts with bioclasts filling burrows; 3 = silts with mollusks dispersed in matrix; 4 = silty sands with bioclasts dispersed or concentrated.

Valves = Number of valves used in each sample. If a sample contained less than 30 valves (left or right) all were measured. For *C. sericea*, if a sample contained more than 30 right valves, 30 were randomly selected. For *C. viminea*, if a sample contained more than

30 left or right valves, 30 of each were randomly selected. All selected valves were measured but due to missing data on less than pristine valves, not all may have been incorporated into the principal components analyses (PCA).

<i>Corbula (Caryocorbula) sericea</i>					
section	sample	formation	age	environment	valves
Cana	NMB 16865	Gurabo	Pliocene	Intermediate	3
Cana	NMB 17009	Gurabo	Pliocene	Intermediate	4
Cana	NMB 16848	Cercado	Miocene	Brackish	25
Cana	TU 1230	Cercado	Miocene	Shallow	15
Cana	UW 1863/27	Cercado	Miocene	Shallow	22
Cana	NMB 16855	Cercado	Miocene	Shallow	27
Gurabo	NMB 15833	Mao	Pliocene	Deep	7
Gurabo	TU 1352	Mao	Pliocene	Deep	10
Gurabo	NMB 15805	Gurabo	Pliocene	Deep	24
Gurabo	NMB 15842	Gurabo	Miocene	Intermediate	10
Gurabo	NMB 15846	Gurabo	Miocene	Intermediate	10
Gurabo	NMB 15863	Gurabo	Miocene	Intermediate	12
Gurabo	NMB 16810	Gurabo	Miocene	Intermediate	17
Gurabo	NMB 15869	Gurabo	Miocene	Intermediate	21
Gurabo	NMB 15911	Cercado	Miocene	Shallow	1
Gurabo	NMB 15912	Cercado	Miocene	Shallow	1
Mao	NMB 16910		Miocene	Intermediate	5
Mao	NMB 16802		Miocene	Intermediate	7
Mao	NMB 16929		Miocene	Shallow	24
Mao	NMB 16928		Miocene	Shallow	25
Mao	UW 1863/25		Miocene	Shallow	25
Mao	UW 1863/26		Miocene	Shallow	23
Mao	NMB 16913		Miocene	Shallow	23
Yaque	TU 1206		Pliocene	Deep	16
Zalaya	TU 1227A		Pliocene	Deep	27
Yaque	TU 1403		Pliocene	Deep	16
Yaque	NMB 17278		Miocene	Shallow	2
Yaque	NMB 17273		Miocene	Brackish	3

<i>Corbula (Bothrocorbula) viminea</i>					
section	sample	formation	age	sed. type	valves
Cana	NMB 16833	Gurabo	Miocene	3	28
Cana	NMB 16832	Gurabo	Miocene	3	5
Cana	NMB 16837	Cercado	Miocene	3	9
Cana	NMB 16838	Cercado	Miocene	3	3
Cana	TU 1230	Cercado	Miocene	3	53
Cana	NMB 16857	Cercado	Miocene	1	10
Cana	NMB 17005	Cercado	Miocene	1	4
Gurabo	NMB 15878	Gurabo	Miocene	1	4
Gurabo	TU 1297	Gurabo	Miocene	2	7
Gurabo	NMB 15882	Gurabo	Miocene	2	4
Gurabo	NMB 15906	Cercado	Miocene	1	47
Gurabo	NMB 15900	Cercado	Miocene	1	37
Mao	NMB 16915		Miocene	1	4
Mao	NMB 16917		Miocene	1	14
Mao	NMB 16923		Miocene	1	21
Mao	NMB 16927		Miocene	1	1
Yaque	TU 1445		Miocene	—	2
Yaque	NMB 16938	Baitoa	Miocene	3	5
Yaque	NMB 16936	Baitoa	Miocene	3	1
Yaque	NMB 16935	Baitoa	Miocene	4	1
Yaque	NMB 17289	Baitoa	Miocene	4	2
Yaque	TU 1364	Baitoa	Miocene	4	9
Yaque	TU 1363	Baitoa	Miocene	4	2
Yaque	NMB 17288	Baitoa	Miocene	3	2
Yaque	NMB 17286	Baitoa	Miocene	4	1





PLATES


EXPLANATION OF PLATE 1

Figure

Page

- 1-8, 10, 11, 13, 14. **Corbula (Bothrocorbula) viminea** Guppy, 1866b 12
- 1, 4. Hypotype. NMB G 14110; from locality TU 1364: Río Yaque del Norte, upper Lower to lower Middle Miocene Baitoa Formation. Right valve: 1. interior, $\times 4\frac{1}{3}$; 4. exterior, $\times 4$. Length, 14.0 mm; height, 9.7 mm; width, 4.8 mm.
- 2, 5. Hypotype. NMB G 14109; from locality TU 1364: Río Yaque del Norte, upper Lower to lower Middle Miocene Baitoa Formation. Left valve: 2. interior, $\times 4\frac{1}{3}$; 5. exterior, $\times 4\frac{2}{3}$. Length, 13.3 mm; height, 9.3 mm; width, 3.8 mm.
3. Syntype. BMNH 64088. Bowden Formation, Jamaica. Right valve exterior. Length, 19.1 mm; height, 13.9 mm; width, 6.3 mm; $\times 3$.
6. Syntype. BMNH 64099. Bowden Formation, Jamaica. Left valve exterior. Length, 15.1 mm; height, 10.3 mm; width, 5.0 mm; $\times 3$.
7. Hypotype. NMB G 14108; from locality TU 1230: Río Cana, Upper Miocene Cercado Formation. Right valve exterior. Length, 14.2 mm; height, 9.9 mm; width, 5.2 mm; $\times 4$.
8. Hypotype. NMB G 14107; from locality TU 1230: Río Cana, Upper Miocene Cercado Formation. Left valve exterior. Length, 14.1 mm; height, 9.7 mm; width, 5.0 mm; $\times 4\frac{1}{3}$.
10. Hypotype. NMB G 14106; from locality NMB 15900: Río Gurabo, Upper Miocene Cercado Formation. Right valve exterior. Length, 16.3 mm; height, 11.5 mm; width, 6.0 mm; $\times 3$.
11. Hypotype. NMB G 14105; from locality NMB 15900: Río Gurabo, Upper Miocene Cercado Formation. Left valve exterior. Length, 15.3 mm; height, 11.3 mm; width, 5.4 mm; $\times 3$.
13. Hypotype. NMB G 14104; from locality NMB 16923: Río Mao, Upper Miocene Cercado Formation (Maury's Bluff 3). Right valve exterior. Length, 17.4 mm; height, 12.3 mm; width, 6.0 mm; $\times 4$.
14. Hypotype. NMB G 14103; from locality NMB 16923: Río Mao, Upper Miocene Cercado Formation (Maury's Bluff 3). Left valve exterior. Length, 15.9 mm; height, 11.8 mm; width, 4.9 mm; $\times 4$.
- 9, 12. **Corbula (Caryocorbula) dominicensis** Gabb, 1873b 14
- 9, 12. Hypotype. NMB G 14111; from locality NMB 17821: Río Yaque del Norte, upper Lower to lower Middle Miocene Baitoa Formation. Articulated shell: 9. right side; 12. left side. Length, 15.3 mm; height, 9.2 mm; width, 6.9 mm; $\times 4\frac{1}{3}$.





EXPLANATION OF PLATE 2

Figure		Page
1, 2, 4, 5.	Corbula (Caryocorbula) dominicensis Gabb, 1873b	14
1, 4.	Hypotype. NMB G 14113; from locality TU 1226: Río Yaque del Norte, upper Lower to lower Middle Miocene Baitoa Formation. Right valve: 1. interior; 4. exterior. Length, 14.2 mm; height, 9.0 mm; width, 4.0 mm; $\times 4\frac{1}{3}$.	
2, 5.	Hypotype. NMB G 14112; from locality TU 1226: Río Yaque del Norte, upper Lower to lower Middle Miocene Baitoa Formation. Left valve: 2. interior; 5. exterior. Length, 13.6 mm; height, 8.2 mm; width, 3.1 mm; $\times 4\frac{1}{3}$.	
3, 6.	?Corbula (Caryocorbula) dominicensis Gabb, 1873b	14
3.	Hypotype. PRI 29033. Río Cana, Upper Miocene Cercado Formation; figured in Maury (1917). Left valve exterior. Length, 13.4 mm; height, 8.6 mm; width, 3.3 mm; $\times 4\frac{1}{3}$.	
6.	Hypotype. PRI 29033. Río Cana, Upper Miocene Cercado Formation; figured in Maury (1917). Right valve exterior. Length, 12.6 mm; height, 8.6 mm; width, 3.2 mm; $\times 4\frac{1}{3}$.	
7-21.	Corbula (Caryocorbula) sericea Dall, 1898	15
7.	Lectotype. USNM 135655. Moín Formation, Limón, Costa Rica. Right valve exterior. Length, 5.3 mm; height, 4.0 mm; width, 2.0 mm; $\times 4\frac{1}{3}$.	
8.	Syntype of <i>Corbula (Cuneocorbula) cercadica</i> Maury, 1917 (misabeled as <i>Corbula (Cuneocorbula) caimitica</i> Maury, 1917). PRI 29035. Río Mao, Upper Miocene Cercado Formation (Maury's Bluff 3). Right valve exterior. Length, 6.6 mm; height, 4.6 mm; width, 2.3 mm; $\times 4\frac{1}{3}$.	
9.	Syntype of <i>Corbula (Cuneocorbula) cercadica</i> Maury, 1917 (misabeled as <i>Corbula (Cuneocorbula) caimitica</i> Maury, 1917). PRI 29035. Río Mao, Upper Miocene Cercado Formation (Maury's Bluff 3). Left valve exterior. Length, 5.6 mm; height, 3.9 mm; width, 2.0 mm; $\times 5\frac{2}{3}$.	
10, 14.	Hypotype. NMB G 14119; from locality NMB 16848: Río Cana, Upper Miocene Cercado Formation. Right valve: 10. interior, $\times 4\frac{1}{3}$; 14. exterior, $\times 5\frac{2}{3}$. Length, 7.0 mm; height, 5.0 mm; width, 3.0 mm.	
11, 15.	Hypotype. NMB G 14118; from locality NMB 16848: Río Cana, Upper Miocene Cercado Formation. Left valve: 11. interior, $\times 4\frac{1}{3}$; 15. exterior, $\times 5\frac{2}{3}$. Length, 7.5 mm; height, 4.7 mm; width, 2.4 mm.	
12.	Hypotype. NMB G 14121; from locality NMB 16855: Río Cana, Upper Miocene Cercado Formation. Right valve exterior. Length, 8.1 mm; height, 4.8 mm; width, 2.7 mm; $\times 5\frac{2}{3}$.	
13.	Hypotype. NMB G 14120; from locality NMB 16855: Río Cana, Upper Miocene Cercado Formation. Left valve exterior. Length, 7.1 mm; height, 4.6 mm; width, 2.3 mm; $\times 5\frac{2}{3}$.	
16.	Hypotype. NMB G 14115; from locality NMB 16928: Río Mao, Upper Miocene Cercado Formation (Arroyo Bajón). Right valve exterior. Length, 6.1 mm; height, 4.5 mm; width, 2.1 mm; $\times 5\frac{2}{3}$.	
17.	Hypotype. NMB G 14114; from locality NMB 16928: Río Mao, Upper Miocene Cercado Formation (Arroyo Bajón). Left valve exterior. Length, 5.6 mm; height, 4.0 mm; width, 1.8 mm; $\times 6\frac{1}{3}$.	
18.	Hypotype. NMB G 14117; from locality NMB 15869: Río Gurabo, Upper Miocene part of Gurabo Formation. Right valve exterior. Length, 4.9 mm; height, 3.2 mm; width, 1.6 mm; $\times 6\frac{1}{3}$.	
19.	Hypotype. NMB G 14116; from locality NMB 15869: Río Gurabo, Upper Miocene part of Gurabo Formation. Left valve exterior. Length, 4.2 mm; height, 2.9 mm; width, 1.4 mm; $\times 6\frac{1}{3}$.	
20.	Hypotype. NMB G 14123; from locality TU 1227A: Cañada Zalaya, Lower Pliocene part of Gurabo Formation. Right valve exterior. Length, 6.0 mm; height, 4.2 mm; width 2.3 mm; $\times 5\frac{2}{3}$.	
21.	Hypotype. NMB G 14122; from locality TU 1227A: Cañada Zalaya, Lower Pliocene part of Gurabo Formation. Left valve exterior. Length, 5.6 mm; height, 3.9 mm; width 2.0 mm; $\times 5\frac{2}{3}$.	
22-26.	Corbula (Juliacorbula) fossilis Pilsbry, 1922	17
22, 23.	Holotype. ANSP 2689; Dominican Republic (locality unknown). Right valve: 1. exterior, 2. interior. Length, 8.7 mm; height, 6.1 mm; width, 2.7 mm; $\times 4$.	
24.	Paratype. ANSP uncataloged; Dominican Republic (locality unknown). Left valve exterior. Length, 8.4 mm; height, 5.8 mm; width, 2.8 mm; $\times 5\frac{1}{3}$.	
25.	Hypotype. NMB G 14125; from locality NMB 16817: Río Cana, Lower Pliocene part of Gurabo Formation. Right valve exterior. Length, 5.6 mm; height, 3.7 mm; width, 1.4 mm; $\times 7\frac{1}{3}$.	
26.	Hypotype. NMB G 14124; from locality NMB 15914: Río Gurabo, Upper Miocene Cercado Formation. Right valve exterior. Length, 5.7 mm; height, 4.1 mm; width, 1.6 mm; $\times 6\frac{2}{3}$.	







EXPLANATION OF PLATE 3

Figure

Page

19

- 1-10. **Corbula (Panamicorbula) canae** new species 19
- 1, 2. Holotype. NMB G 14126; from locality NMB 16845: Río Cana, Upper Miocene Cercado Formation. Articulated shell: 1. right side; 2. left side. Length, 14.4 mm; height, 11.8 mm; width, 9.6 mm; $\times 3\frac{2}{3}$.
- 3, 4. Paratype. NMB G 14130; from locality NMB 16841: Río Cana, Upper Miocene Cercado Formation. Right valve: 3. exterior, 4. interior. Length, 12.4 mm; height, 10.2 mm; width, 3.4 mm; $\times 4\frac{1}{3}$.
5. Paratype. NMB G 14129; from NMB 16841: Río Cana, Upper Miocene Cercado Formation. Right valve exterior. Length, 13.9 mm; height, 11.2 mm; width 4.8 mm, $\times 4\frac{1}{3}$.
- 6, 7. Paratype. NMB G 14127; from locality NMB 16841: Río Cana, Upper Miocene Cercado Formation. Left valve: 6. exterior, 7. interior. Length, 12.2 mm; height, 9.9 mm; width, 3.6 mm; $\times 4\frac{1}{3}$.
8. Paratype. NMB G 14128; from NMB 16841: Río Cana, Upper Miocene Cercado Formation. Left valve exterior. Length, 13.5 mm; height, 10.4 mm; width 4.3 mm; $\times 4\frac{1}{3}$.
9. Hypotype. NMB G 14131; from NMB 16841: Río Cana, Upper Miocene Cercado Formation. Left valve exterior. Length, 8.3 mm; height, 7.0 mm; width, 2.3 mm; $\times 4\frac{1}{3}$.
10. Hypotype. NMB G 14132; from NMB 16841: Río Cana, Upper Miocene Cercado Formation. Right valve exterior. Length, 7.1 mm; height, 5.5 mm; width, 1.5 mm; $\times 4\frac{1}{3}$.
11. **Corbula (Panamicorbula) sp.** 19
11. Hypotype. NMB G 14133; from locality NMB 16990: Río Cana, Upper Miocene Cercado Formation. Length, 5.4 mm; height, 4.0 mm; width, 1.3 mm; $\times 4\frac{1}{3}$.
- 12-18. **Corbula (Varicorbula) sanctidominici** Maury, 1925 19
12. Holotype. PRI 903. Río Cana, Cercado Formation. Right valve exterior. Length, 9.5 mm; height, 9.6 mm; width, 5.1 mm, $\times 4\frac{1}{3}$.
- 13, 18. Hypotype. NMB G 14135; from locality NMB 16837: Río Cana, Upper Miocene Cercado Formation. Right valve: 13. exterior, $\times 4\frac{2}{3}$; 18. interior, $\times 4\frac{1}{3}$. Length, 7.8 mm; height, 7.9 mm; width, 4.6 mm.
14. Hypotype. NMB G 14136; from locality TU 1250: Río Verde, Lower Pliocene part of Gurabo Formation. Right valve exterior. Length, 5.5 mm; height, 5.4 mm; width, 2.6 mm, $\times 4\frac{1}{3}$.
15. Hypotype. NMB G 14137; from locality TU 1250: Río Verde, Lower Pliocene part of Gurabo Formation. Right valve exterior. Length, 4.4 mm; height, 4.1 mm; width, 2.0 mm, $\times 4\frac{1}{3}$.
- 16, 17. Hypotype. NMB G 14134; from locality NMB 16837: Río Cana, Upper Miocene Cercado Formation. Left valve: 16. exterior, $\times 4.7$, 17. interior, $\times 6\frac{2}{3}$. Length, 4.6 mm; height, 4.0 mm; width, 1.7 mm.



The first part of the history of the American people is the story of the early settlers. They came from Europe and brought with them the customs and traditions of their native land. They were the first to build a new home in a new world. They were the first to plant the seeds of a new nation. They were the first to create a new way of life. They were the first to show the world that a new people could be born.

The second part of the history of the American people is the story of the growth of the nation. The settlers grew in number and in power. They fought for their rights and won. They built a government that was based on the principles of liberty and justice. They created a new society that was free from the oppression of the old world. They were the first to show the world that a new people could be born.

The third part of the history of the American people is the story of the development of the nation. The settlers grew in number and in power. They fought for their rights and won. They built a government that was based on the principles of liberty and justice. They created a new society that was free from the oppression of the old world. They were the first to show the world that a new people could be born.

The fourth part of the history of the American people is the story of the future of the nation. The settlers grew in number and in power. They fought for their rights and won. They built a government that was based on the principles of liberty and justice. They created a new society that was free from the oppression of the old world. They were the first to show the world that a new people could be born.

INDEX

Note: Page numbers are in light face; plate numbers are in **bold** face type; pages on which principal discussion occur are in *italics*.

- Adams (1852a) 18,19
 Adams (1852b) 17
aequalis,
 Corbula (Panamicorbula) 19
 Potamomya 18
aequivalvis,
 Corbula 17
 Corbula (Juliacorbula) 17,18
 Juliacorbula 17
 aff. *C. inflata*,
 Corbula (Panamicorbula) 19
 Agueguexquite Formation 11
 Alabama 14
alabamiensis,
 Corbula 14
 Allmon, Warren 6,16
 Aloidis Megerle von Mühlfeldt, 1811 12
 Amphistegina Orbigny, 1826 26
 Anadara Gray, 1847 26
 grandis (Broderip and Sowerby, 1829) 9
 patricia (Sowerby, 1850) 9,20,26
 Anderson (1991) 11
 Anderson (1994) 6,8-12,15,16,19,20
 Angostura Formation 15
 ANSP (Academy of Natural Sciences of Philadelphia,
 Philadelphia, PA, U.S.A.) 6,11,14,15,18,21
 "Arca" beds 9,19
 Baitoa Formation 5,10,14,15,17,22,26
 Benamy, Elana 6
 Bermont Formation 13
 Blow, Warren 6
 BMNH (Natural History Museum, London, U.K.) 6,11,13
 Bold (1988) 9,26
 Boss (1982) 12
 Bowden Formation 5,11-14,17,22
 Broderip and Sowerby (1829) 9
 Brown and Pilsbry (1911) 17
 Bruguière (1797) 12
 Budd et al. (1996) 7,8
caimitica,
 Corbula (Cuneocorbula) 15,16
 Caloosahatchee Formation 13
canae,
 Corbula (Panamicorbula) 3,5,6,8,19,20
caribaea pergrata,
 Corbula (Caryocorbula) 16
 Caribbean Sea 11
 Caudites Coryell and Fields, 1937 26
 Central America 5,12,17,19,22
cercadica,
 Corbula (Caryocorbula) 15
 Corbula (Cuneocorbula) 15,16
 Cercado Formation 5,7,8,11,14,15,17-22,26
 Chipola Formation 13
 Claibornian Stage 14
contracta,
 Corbula 17
 Corbulidae Lamarck, 1818 5,12
 Corbulinae Lamarck, 1818 12
Corbula Bruguière, 1797 5,7,8,11,12
 aequivalvis Philippi, 1836 17
 alabamiensis Lea, 1833 14
 contracta Say, 1822 17
 cubaniana Orbigny, 1846 17
 disparilis Orbigny, 1846 20
 dominicensis Gabb, 1873b 14
 knoxiana Adams, 1852b 17
 knoxiana fossilis Pilsbry, 1922 17
 lavaleana Orbigny, 1846 15
 macdonaldi Dall, 1912 18
 sericea Dall, 1898 15
 sulcata Lamarck, 1801 12
 vieta Guppy, 1866a 20
 viminea Guppy, 1866b 12
Corbula (Aloidis) Megerle von Mühlfeldt, 1811
 vieta Guppy, 1866a 20
 sancti-dominici Maury, 1925 20
Corbula (Bothrocorbula) Gabb, 1873a 5,11,12
 radiatula Dall, 1898 13
 synarmostes Dall, 1898 13
 viminea Guppy, 1866b 1,5,6,7-14,15,26
 wilcoxii Dall, 1898 13
Corbula (Caryocorbula) Gardner, 1926 5,11,14,17,20
 caribaea pergrata Maury, 1925 16
 cercadica Maury, 1917 15
 daphnis Maury, 1925 16
 democracia F. Hodson, 1931 15
 dominicensis Gabb, 1873b 1,2,5,14-15
 dominicensis veracruzana Perrilliat, 1984 15
 helenae Maury, 1912 16
 manzanillensis Maury, 1925 17
 oropendula Olsson, 1922 17
 oropendula dolicha (Woodring, 1982) 17
 oropendula stena (Woodring, 1982) 17
 prenasuta Olsson, 1964 15
 sericea Dall, 1898 2,5,6,7-11,15-17,26
 smithiana Maury, 1912 16
Corbula (Corbula) Bruguière, 1797
 sericea Dall, 1898 15
 sulcata (Lamarck, 1801) 12
Corbula (Cuneocorbula) Cossmann, 1886 14
 caimitica Maury, 1917 15,16
 cercadica Maury, 1917 15,16
 cubaniana Orbigny, 1846 17
 dominicensis Gabb, 1873b 14
Corbula (Hexacorbula) Olsson, 1932 12
Corbula (Juliacorbula) Olsson and Harbison, 1953 5,11,17
 aequivalvis Philippi, 1836 17,18
 cubaniana Orbigny, 1846 17,18
 fossilis Pilsbry, 1922 2,5,7,8,17-18
 knoxiana Adams, 1852b 18
 scutata Gardner, 1943 18
Corbula (Notocorbula) Iredale, 1930 11,20
 vicaria (Iredale, 1930) 20
Corbula (Panamicorbula) Pilsbry, 1932 5,11,18-19,20
 aequalis (Adams, 1852a) 19
 aff. *C. inflata* (Adams, 1852a) 19
 canae n. sp. 3,5-8,19,20

- inflata* (Adams, 1852a) 19
macdonaldi Dall, 1912 19
 sp. 3,19-20
trigonalis (Adams, 1852a) 19
Corbula (*Serracorbula*) Olsson, 1961 11
Corbula (*Tenuicorbula*) Olsson, 1932 11
Corbula (*Varicorbula*) Grant and Gale, 1931 5,11,20,21,22
disparilis Orbigny, 1846 21,22
gibba (Olivi, 1792) 20
heterogena Guppy (in Dall, 1898) 11,22
operculata Philippi, 1848 21
philippii Smith, 1885 21
sanctianderaea Maury, 1925 22
sanctidominici Maury, 1925 3,5-8,11,20-22
vieta Guppy, 1866a 20,21
waltonensis Gardner, 1928 22
 Cossmann (1886) 14
 Costa Rica 11,14,15,17,19,22
 Limón 15,16
 Limón Basin 5,11
 Punta Judas 11,19
cubaniana,
 Corbula 17
 Corbula (*Cuneocorbula*) 17
 Corbula (*Juliacorbula*) 17,18
Cytherella Jones, 1849 26

 Dall (1890-1903) 5,11,13-15,21,22
 Dall (1912) 18,19
daphnis,
 Corbula (*Caryocorbula*) 16
democracia,
 Corbula (*Caryocorbula*) 15
disparilis,
 Corbula 20
 Corbula (*Varicorbula*) 21,22
 Dominican Republic 5,6,11,12,14,15,17-22
 Cibao Valley 5,6
 Arroyo Bajón 14,17,22
 Arroyo Ballaco 22
 Arroyo López 17,22
 Cañada Zalaya 6,9,16,17,22,26
 Río Amina 6,13,14,16,17
 Río Cana 5-10,13-22,26
 Caimito 15,21
 Río Gurabo 6,8-11,13,14,16-18,22,26
 Río Mao 6,9-11,13,14,16,17,22,26
 Bluff 1 of Maury (1917) 17,22
 Bluff 2 of Maury (1917) 14,17,22
 Bluff 3 of Maury (1917) 14,17
 Río Verde 6,16,17,22
 Río Yaque del Norte 5,6,9-11,13-17,22,26
 Angostura 14,17
 López 9,14,22
 La Barranca 17,22
 Santiago 6,17,22
dominicensis,
 Corbula 14
 Corbula (*Caryocorbula*) 1,2,5,14-15
 Corbula (*Cuneocorbula*) 14
dominicensis veracruzana,
 Corbula (*Caryocorbula*) 15

 East Asia 14
 eastern Pacific Ocean 5,9,11,17-20

 Panamic Province 11,18
 Ecuador 15
Erycina Lamarck, 1805
 tensa Guppy, 1866a 21
 Europe 20

 Florida 5,11-13,17,18,22
fossilis,
 Corbula (*Juliacorbula*) 2,5,17-18

 Gabb (1873a) 11,12
 Gabb (1873b) 5,14,15,17,20,21
 Gabb (1881) 15
 Gardner (1926) 11,12,14
 Gardner (1928) 11,22
 Gardner (1943) 18
 Gatun Formation 5,11,15,17
 Geological Society of America 6
gibba,
 Corbula (*Varicorbula*) 20
 Tellina 20
grandis,
 Anadara 9
 Grant and Gale (1931) 11,20
 Guppy (1866a) 21
 Guppy (1866b) 5,12,13
 Guppy (1876) 14
 Guppy (in Dall, 1898) 11,22
 Gurabo Formation 5,7,8,14,17,18,22,26

 Haiti 6,14
helenae,
 Corbula (*Caryocorbula*) 16
heterogena,
 Corbula (*Varicorbula*) 11,22
 Hodson and Hodson (1931) 15

 IGM (Intituto de Geología, Ciudad Universitaria de México, D.F., Mexico) 11,18
inflata,
 Corbula (*Panamicorbula*) 19
 Potamomya 18
 Iredale (1930) 11,20

 Jamaica 5,11-14,17,22
 Jeffery, Paul 6
Juliacorbula Olsson and Harbison, 1953
 aequivalvis (Philippi, 1836) 17
 Jung (1969) 11,16-18,20
 Jung (1986) 21
 Jung, Peter 6

 Keen (1971) 19,21
knoxiana fossilis,
 Corbula 17
knoxiana,
 Corbula 17
 Corbula (*Juliacorbula*) 18
 Corbula (*Juliacorbula*) 6
 Kool, Silvard 26
Krithe Brady, Crosskey, and Robertson, 1874 26

 l'Enfer Formation 11,18,19
 Courbaril Sand and Clay Member 18
 Lamarck (1799) 12
 Lamarck (1801) 12

- Lamarck (1818) 12
- Larkinia* Reinhert, 1935 26
- Las Canobas Formation 14
- lavaleana*,
- Corbula* 15
- Lea (1833) 14
- Lewy and Sambleton (1979) 12
- Loxoconcha* Sars, 1866 26
- Lyria* Gray, 1847 26
- macdonaldi*,
- Corbula* 18
- Corbula* (*Panamicorbula*) 19
- Manzanilla Formation 11,17,21,22
- manzanillensis*,
- Corbula* (*Caryocorbula*) 17
- Mao Formation 5,7,8,14,17,26
- Mao Adentro Limestone Member 14
- Maury (1912) 16
- Maury (1917) 12-17,20,21
- Maury (1922) 9
- Maury (1925) 5,11,12,16-18,20-22
- McLean (1951) 17
- Mediterranean Sea 20
- Megerle von Mühlfeldt (1811) 12
- Melongena* Schumacher, 1817 26
- Mexico 11,15,18
- Coatzacoalcos 11
- Veracruz 11,15,18
- miliolid* 26
- Moín Formation 16,17
- Moore (1969) 12,14,17,18,20
- Museum of Comparative Zoology, Harvard University,
 Cambridge, MA, U.S.A. 6
- Mytilus* Linnaeus, 1758 26
- National Science Foundation 6
- NMB (Naturhistorisches Museum, Basel, Switzerland) .. 6,11,13-22
- North America 14,20
- Oak Grove Formation 13
- Oliva* Bruguière, 1789 26
- Olivi (1792) 20
- Olsson (1922) 11,12,17
- Olsson (1932) 9,11,12
- Olsson (1961) 9,11,17,18
- Olsson (1964) 15
- Olsson and Harbison (1953) 11,17
- operculata*,
- Corbula* (*Varicorbula*) 21
- Orbigny (1846) 17,21
- oropendula*,
- Corbula* (*Caryocorbula*) 17
- oropendula dolicha*,
- Corbula* (*Caryocorbula*) 17
- oropendula stena*,
- Corbula* (*Caryocorbula*) 17
- Pachycrommium* 26
- Paleontological Society 6
- Panama 11,15,17,18,22
- Paracytheridea* Müller, 1894 26
- patricia*,
- Anadara* 9,20,26
- Perrilliat (1984) 11,15,17,18
- Peru 11,18
- Philippi (1836) 17,18
- Philippi (1848) 21
- philippii*,
- Corbula* (*Varicorbula*) 21
- Pilsbry (1922) 5,12,14,15,17,18,20,21
- Pilsbry (1932) 11,18,19
- Polyštira* Woodring, 1928 26
- Potamomya* Sowerby, 1839
- aequalis* Adams, 1852a 18
- inflata* Adams, 1852a 18
- trigonalis* Adams, 1852a 18
- prenasuta*,
- Corbula* (*Caryocorbula*) 15
- PRI (Paleontological Research Institution, Ithaca, NY, U.S.A.)
 6,11,13,15,16,18,21
- Proteoconcha* Plusquellec and Sandberg, 1969 26
- pteropod 26
- radiatula*,
- Corbula* (*Bothrocorbula*) 13
- Radimella* Pokorny, 1968 26
- Ramírez (1950) 12
- Río Banano Formation 14
- Rios (1975) 17
- Rosenberg, Gary 6,14
- sanctianderaea*,
- Corbula* (*Varicorbula*) 22
- sancti-dominici*,
- Corbula* (*Aloidis*) 20
- sanctidominici*,
- Corbula* (*Varicorbula*) 3,5,6,8,11,20-22
- Santa Rosa beds 11,15,18
- Saunders et al. (1986) 5,6,9,11,14,15,17-20,22,26
- Schmidt (1818) 12
- Schneider, Jay 6
- scutata*,
- Corbula* (*Juliacorbula*) 18
- Senegal 12
- sericea*,
- Corbula* 15
- Corbula* (*Caryocorbula*) 2,5,6,7-11,15-17,26
- Corbula* (*Corbula*) 15
- Seyfried et al. (1985) 11,19
- Sigma Xi 6
- Smith (1885) 21
- smithiana*,
- Corbula* (*Caryocorbula*) 16
- soritid 26
- South America 14,17
- Sowerby (1850) 9
- Springvale Formation 11,18,19
- Melajo Clay Member 18
- Stenzel et al. (1957) 20
- Stewart (1930) 12
- Stigmaulux* Mörch, 1852 26
- Strombina* Mörch, 1852 26
- Strombus* Linnaeus, 1758 26
- sulcata*,
- Corbula* 12
- Corbula* (*Corbula*) 12

- synarmostes*,
Corbula (Bothrocorbula) 13
- Talparo Formation 18
 Matura Sand and Clay Member 18
- Taylor, Paul 6
- Tellina* Linnaeus, 1758 26
gibba Olivi, 1792 20
- tensa*,
Erycina 21
- Thomonde Formation 14
- Thompson, Jann 6
- trigonalis*,
Corbula (Panamicorbula) 19
Potamomya 18
- Trinidad 5,11,16-19,21,22
- TU (Tulane University, New Orleans, LA, U.S.A.) .. 6,11,13-17,21,22
- USNM (United States National Museum of Natural History,
 Washington, DC, U.S.A.) 6,11,13,15,16,18,19,21
- UW (Museum of Geology, University of Wisconsin-Madison,
 Madison, WI, U.S.A.) 6,11,16
- Vaught (1989) 11
- Venezuela 11,15
 Falcón 15
- vicaria*,
Corbula (Notocorbula) 20
- vieta*,
Corbula 20
Corbula (Aloidis) 20
Corbula (Varicorbula) 20,21
- viminea*,
Corbula 12
Corbula (Bothrocorbula) 1,5,6,8-14,15,26
- Vokes, E. (1989) 11
- Vokes, H. (1945) 12,18,19
- Vokes, H. (1980) 12
- Vokes, H. (1989) 13,15
- Vokes, Emily 6
- Waller, Thomas 6
- waltonensis*,
Corbula (Varicorbula) 22
- Weisbord (1964) 17,20,21
- West Indies 12,17
- western Atlantic Ocean 11,21
- western Pacific Ocean 20
- Westphal, Klaus 6
- wilcoxii*,
Corbula (Bothrocorbula) 13
- Woodring (1925) 12-15
- Woodring (1973) 9
- Woodring (1982) 11,17,20-22
- Woodring et al. (1924) 14
- Yonge (1946) 20
- Zone H of Maury (1917) 15