



OPEN

Polystyrene nanoplastics and microplastics can act as Trojan horse carriers of benzo(a)pyrene to mussel hemocytes in vitro

Alberto Katsumiti^{1,2,3}, María Paula Losada-Carrillo^{1,3}, Marta Barros¹ & Miren P. Cajaraville^{1✉}

In this work we studied the ability of polystyrene (PS) nanoplastics (NPs) and microplastics (MPs) to transfer benzo(a)pyrene (BaP) to mussel hemocytes and to produce toxic effects in vitro. For this, intracellular fate and toxicity of PS NPs (0.05 μm) and MPs (0.5 and 4.5 μm) alone or with BaP and of BaP alone were assessed. Particles of 0.05 and 0.5 μm largely aggregated in the exposure medium whereas presence of BaP reduced particle aggregation. Cells internalized PS NPs and MPs alone or with BaP and these were found inside and outside lysosomes, depending on their size. PS particles alone or with BaP were cytotoxic to hemocytes only at the highest concentrations tested. The same was true for most sublethal endpoints except for increased phagocytic activity provoked by NPs and 0.5 μm MPs at lower concentrations. Plastic particles appeared to be the main drivers for reduced plasma membrane integrity and increased phagocytic and lysosomal activities whereas BaP appeared to contribute more to reduced cell viability and phagocytosis and increased ROS production and genotoxicity. Overall, PS NPs and MPs can act as carriers of BaP to mussel hemocytes, rising concerns about risks plastics associated to pollutants may pose to aquatic organisms.

Nowadays, approximately 300 million tons of plastic are produced worldwide every year and more than 8 million tons of plastic end up in the ocean¹. Due to its durability, it is estimated that all plastic ever produced still remains in the environment².

In the marine environment, the most abundant plastic polymers are polystyrene (PS), polyethylene (PE), polypropylene (PP), the group of polyesters, polyamide and acrylics (PP&A) and polyvinyl chloride (PVC)^{2,3}. These plastics can be found in the marine environment as large plastic pieces and as small fragments such as microplastics (MPs, < 5 mm) or nanoplastics (NPs, < 100 nm)^{4,5}.

In the last years, NP and MP pollution has received special attention since they can easily accumulate and are difficult to remove from the environment and because they are more bioavailable to marine organisms than larger plastics^{2,6}. Both NPs and MPs can be found in large quantities depending on the area. For instance, in heavily populated coastal areas in China, MP concentration is estimated to vary from 545 to 4137.3 particles/m³⁷. In other populated areas in Japan, Europe and North America, MP concentration is estimated to be lower (up to 1.5 particles/m³ in northwest Europe)⁷. In the northeast Atlantic Ocean (Bay of Biscay), MP concentration varies from 0.00098 to 0.35 particles/m³³. Nevertheless, due to lack of standardized methodology for sampling, extraction and analysis of MPs in environmental samples, it is difficult to determine actual exposure concentrations and levels of MPs accumulated in biota, but recent studies showed that the size fraction below 150 μm in size is being overlooked in most published studies relying on FTIR for polymer identification⁸.

Due to their small size, MPs can be easily confounded as food particles by many marine organisms, such as zooplankton, fish, mammals and specially by filter-feeder organisms such as bivalves^{9–12}. In marine bivalves, in vivo studies have reported that exposure to NPs and MPs may cause harmful effects. Decrease in feeding and metabolic rates and in energy reserves have been reported in mussels exposed to NPs and MPs^{11,13}. Adverse effects on growth, development and reproduction have also been associated with the exposure to NPs and MPs¹⁴. At cellular and subcellular levels, in vitro studies in hemocytes have suggested that NPs and MPs are internalized into

¹CBET Research Group, Department Zoology and Animal Cell Biology, Faculty of Science and Technology and Research Centre for Experimental Marine Biology and Biotechnology PiE, University of the Basque Country UPV/EHU, Leioa, Basque Country, Spain. ²Present address: GAIKER Technology Centre, Basque Research and Technology Alliance (BRTA), Zamudio, Spain. ³These authors contributed equally: Alberto Katsumiti and María Paula Losada-Carrillo. ✉email: miren.p.cajaraville@ehu.eus

	Media	Z-average (nm)	Z-potential (mV)
0.05 μm NPs	BME	7700 \pm 283	-22.6 \pm 2.17
	DW	184.3 \pm 82	-10.2 \pm 0.06
0.05 μm NPs + BaP	BME	4889 \pm 305	-22.6 \pm 2.6
	DW	742.6 \pm 56	-13.2 \pm 0.43
0.5 μm MPs	BME	2328 \pm 47	-23.0 \pm 2.36
	DW	742.6 \pm 56	-13.2 \pm 0.43
0.5 μm MPs + BaP	BME	873.6 \pm 35	-24.5 \pm 0.4
	DW	699.2 \pm 47	-10.1 \pm 0.25
4.5 μm MPs	BME	6777 \pm 357	-22.5 \pm 1.99
	DW	5009 \pm 188	-53.7 \pm 0.61
4.5 μm MPs + BaP	BME	5584 \pm 476	-15.2 \pm 0.49
	DW	5237 \pm 75	-50.1 \pm 0.43

Table 1. Hydrodynamic size (Z-average) and surface charge (Z-potential) of NPs and MPs alone or in combination with BaP suspended in supplemented Basal Medium Eagle (BME) and in distilled water (DW). Data are given as mean \pm SD values (n = 3).

the cells via endocytic and non-endocytic pathways, finally accumulating inside lysosomes^{15–17}. Once internalized into the cells, NPs and MPs may cause cytotoxicity, oxidative stress, changes in enzyme activities, lysosomal membrane destabilization, immunotoxicity, genotoxicity and proteomic/transcriptomic changes^{13–24}.

Further, due to their high surface to volume ratio and hydrophobicity, NPs and MPs can adsorb toxic chemicals from the surrounding seawater and transfer them to marine organisms, a phenomenon called “Trojan horse effect”^{25,26}. Several persistent organic pollutants (POPs) such as polycyclic aromatic hydrocarbons (PAHs) have been detected in plastic particles collected from different beaches around the world^{27,28}.

PAHs have been reported to be the most abundant class of POPs adsorbed to plastic particles^{28,29}. Studies have reported PAH concentrations ranging from 1454 to 6002 ng/g in micro-sized pellets collected in the southern coast of Brazil³⁰ and from 35.1 to 8725.8 ng/g in MPs collected from beaches in the Canary Islands²⁸. In other coastal areas and open seas close to China, Japan and the Caribbean Sea, PAH concentrations in MPs ranged from 1 to 9300 ng/g²⁷. In MPs collected in the North Pacific Ocean Gyre, PAH concentrations in MPs ranged from 4 to 846 ng/g²⁹. These MPs may then work as accumulators of large amounts of PAHs, serving as vectors of these toxic compounds to marine organisms.

Different experimental studies *in vivo* have demonstrated the ability of NPs and MPs to transfer PAHs to marine bivalves^{19,22,31–34}. These studies have reported bioaccumulation of PAHs such as pyrene³¹, fluoranthene^{19,33} and benzo(a)pyrene (BaP)^{22,32} in different tissues of bivalves, as well as alterations on different immunological and antioxidant parameters, neurotoxicity and genotoxicity. NPs and MPs may accumulate and transfer different amounts of PAHs to organisms depending on the size of the particles. González-Soto et al.²² reported that smaller PS MPs (0.5 μm) posed an increased hazard in terms of the transfer of BaP to mussel tissues than larger PS MPs (4.5 μm). Similarly, Tang et al.²³ reported that toxicity of BaP was generally aggravated when associated with smaller MPs (500 nm) and mitigated when associated with larger ones (30 μm). Studies have also indicated that additive, synergistic or antagonistic effects of the combination of NPs or MPs and PAHs may occur. In mussels, Avio et al.³¹ reported higher genotoxicity (micronuclei frequency) of PS MPs with pyrene compared to MPs alone. Authors also reported specific modulations in transcriptional responses upon exposure to PS MPs compared to PS MPs with pyrene³¹. Similarly, González-Soto et al.²² reported that PS MPs with BaP induced higher levels of DNA strand breaks compared to PS MPs alone in mussels after 7 days exposure. Despite the relatively large amount of papers published in the last years on the Trojan horse ability of NPs and MPs to transfer PAHs to marine organisms, fundamental questions still remain concerning the intracellular fate and mode of action of NPs and MPs alone or in combination with PAHs.

In this work we aimed to assess the ability of PS NPs (0.05 μm) and MPs (0.5 and 4.5 μm) to transfer BaP to mussel *Mytilus galloprovincialis* hemocytes and to induce toxic effects *in vitro*. For this purpose, intracellular fate was studied by transmission electron microscopy (TEM) and confocal microscopy. Toxic effects of PS NPs and MPs alone or in combination with BaP were determined using *in vitro* assays for cell viability, plasma membrane integrity, phagocytic and lysosomal activities, intracellular ROS production and genotoxicity. Additionally, the behaviour of NPs and MPs alone or in combination with BaP was characterized in different media.

Results

Characterization of NPs and MPs alone or with BaP in different media. Dynamic Light Scattering (DLS) was used to assess hydrodynamic size and surface charge of NPs and MPs alone or in combination with BaP suspended in supplemented Basal Medium Eagle (BME) and distilled water (DW). Results showed marked differences in the aggregation state of the particles in the two media (Table 1). Aggregation was more pronounced in BME than in DW and differences were higher in 0.05 μm NP suspensions (DW: 184.3 nm; BME: 7700 nm) followed by suspensions of 0.5 μm MPs (DW: 742.6 nm; BME: 2328 nm) and 4.5 μm MPs (DW: 5009 nm; BME: 6777 nm) (Table 1). Aggregation was higher in suspensions of particles alone than in preparations with BaP (0.05 μm NPs: 4889 nm, 0.5 μm MPs: 873.6 nm and 4.5 μm MPs: 5584 nm in BME), indicating that presence of BaP may increase the stability of NP and MP suspensions (Table 1).




Figure 1. TEM images showing the intracellular localization of NPs and MPs in mussel hemocytes. (A) control cells, (B–D) hemocytes treated with 10^{12} part./mL of $0.05 \mu\text{m}$ NPs, (E–H) hemocytes treated with 10^9 part./mL of $0.5 \mu\text{m}$ MPs and (I–L) hemocytes treated with 10^8 part./mL of $4.5 \mu\text{m}$ MPs. Red arrows indicate the intracellular localization of NPs at low power magnification. Size of selected NPs and MPs is indicated (red lines). N, nucleus; G, granules; RB, residual bodies.

Concerning surface charge, all particles showed negatively charged surface in both media, with Z-potential values varying from -10.1 to -53.7 mV (Table 1). MPs of $4.5 \mu\text{m}$ showed higher absolute Z-potential values when suspended in DW than in BME, indicating higher stability (Table 1). In the case of $0.05 \mu\text{m}$ NPs and $0.5 \mu\text{m}$ MPs, particles suspended in DW showed lower absolute Z-potential values compared with particles suspended in BME (Table 1). BaP did not influence particles surface charge (Table 1).

Intracellular fate of NPs and MPs alone or with BaP. As seen in the transmission electron microscope (TEM) micrographs, cells treated with NPs and MPs showed signs of increased lysosomal and autophagic activities (Fig. 1). Compared to control cells (Fig. 1A), treated cells showed an increased number of large residual bodies, most containing lipofuscin-like pigment material (Fig. 1B–L). In cells treated with $0.05 \mu\text{m}$ NPs, particles were localized inside residual bodies and free in the cytosol (Fig. 1B–D). In cells treated with $0.5 \mu\text{m}$ MPs, particles were found outside the cells and inside residual bodies and other membrane-bound endo-lysosomal vesicles (Fig. 1E–G). MPs of $0.5 \mu\text{m}$ were also found surrounded and engulfed by cell surface extensions (Fig. 1H). In cells treated with $4.5 \mu\text{m}$ MPs, up to eight particles were found internalized per cell (Fig. 1I, J). MPs of $4.5 \mu\text{m}$ were engulfed through phagocytosis and found inside large membrane-bound phagosomal or phagolysosomal vesicles (Fig. 1K, L).

In the confocal fluorescence microscope images, lysosomes labelled with LysoTracker™ were seen in red (Fig. 2 and supplementary Fig. S1) and BaP fluorescence in blue (Fig. 2E–H and supplementary Fig. S1). As expected, BaP was not detected neither in control cells nor in cells treated with particles alone (Fig. 2A–D and supplementary Figs. S1A–D online). In cells treated with $0.05 \mu\text{m}$ NPs alone, particles were not discernible (Fig. 2B and supplementary Fig. S1B). In cells treated with $0.5 \mu\text{m}$ MPs alone, structures resembling particle aggregates were found in the cytoplasm of the cells and apparently in lysosomes (Fig. 2C and supplementary Fig. S1C). In hemocytes exposed to $4.5 \mu\text{m}$ MPs alone, MPs (up to 6 particles/cell) were easily distinguished in cells cytoplasm surrounded by red fluorescence, thus indicating internalization into lysosomes (Fig. 2D and supplementary Fig. S1D). In cells treated with $0.05 \mu\text{m}$ NPs and $0.5 \mu\text{m}$ MPs with BaP, BaP fluorescence was found in discrete granules in the cytoplasm, some belonging to lysosomes (Fig. 2E, F and supplementary Fig. S1E, F). In cells exposed to $4.5 \mu\text{m}$ MPs with BaP, MPs were found surrounded by red (lysosomes) and blue (BaP) fluorescence (Fig. 2G and supplementary Fig. S1G). In cells treated with BaP alone (Fig. 2H and supplementary Fig. S1H), BaP fluorescence was found mainly internalized into lysosomes, as evidenced by the co-localization of blue and red fluorescence. Overall results show that NPs and MPs are able to carry BaP into the cells.




Figure 2. Confocal fluorescence microscope images showing lysosomes (red) and BaP (blue) in hemocytes exposed to 0.05 μm NPs (10^{12} part./mL) and to 0.5 and 4.5 μm MPs (10^8 and 10^9 part./mL, respectively) alone or in combination with BaP and to BaP alone. Arrowheads indicate structures resembling aggregates of 0.5 μm MPs.

In vitro toxicity. Cell viability. NPs and MPs alone or in combination with BaP showed low cytotoxicity to mussel hemocytes, but treatments with BaP were more toxic than NPs or MPs alone (Fig. 3). Exposures to 0.05 μm NPs alone or with BaP decreased hemocytes viability only at the highest concentration tested (10^{12} part./mL) and cytotoxicity was significantly higher in the same treatment with BaP compared to NPs alone (Fig. 3A). In cells treated with 0.5 μm MPs alone, cell viability decreased only at the highest concentration tested (10^9 part./mL), whereas in cells treated with 0.5 μm MPs with BaP, cell viability decreased at 10^8 and 10^9 part./mL with respect to controls (Fig. 3B). At both 10^8 and 10^9 part./mL, cytotoxicity was significantly higher in treatments with BaP compared to MPs alone (Fig. 3B). In hemocytes treated with 4.5 μm MPs alone or with BaP, cell viability decreased at 10^6 and 10^8 part./mL and cytotoxicity was significantly higher in treatments with BaP compared to MPs alone (Fig. 3C). BaP alone was cytotoxic to hemocytes only at the highest concentration tested (1 μM) compared to controls (Fig. 3A). At equivalent concentrations of BaP, the treatments NPs or MPs with BaP were significantly more toxic than BaP alone (Fig. 3).

Plasma membrane integrity. In exposures to NPs and MPs alone, plasma membrane integrity decreased significantly at 10^{12} part./mL of 0.05 μm NPs, 10^6 , 10^8 and 10^9 part./mL of 0.5 μm NPs and 10^8 part./mL of 4.5 μm MPs with respect to controls (Fig. 4A–C). In cells treated with NPs and MPs with BaP, only 10^8 part./mL of 4.5 μm MPs with BaP significantly disrupted plasma membrane integrity, at levels similar to 4.5 μm MPs alone at the same concentration (Fig. 4C). BaP alone reduced plasma membrane integrity at the three concentrations tested (Fig. 4A–C). At equivalent concentrations of BaP, BaP alone was more toxic than 0.05 μm NPs with BaP but less toxic than 4.5 μm MPs with BaP (Fig. 4A, C).

Phagocytic activity. Treatments with 0.05 μm NPs and 0.5 μm MPs alone increased hemocytes phagocytic activity compared to controls (Fig. 5A, B). Thus, phagocytic activity increased in hemocytes treated with 10^5 to 10^{12} part./mL of 0.05 μm NPs and 10^6 to 10^9 part./mL of 0.5 μm MPs (Fig. 5A, B). In cells exposed to 10^8 part./mL of 4.5 μm MPs alone, phagocytic activity was higher but not significantly different from that in control cells (Fig. 5C). Hemocytes phagocytic activity decreased in exposures to the highest concentrations of NPs and MPs with BaP (Fig. 5A–C). Phagocytic activity was also reduced in treatments to 0.56 and 1 μM of BaP alone (Fig. 5A, B). At equivalent concentrations of BaP, BaP alone inhibited phagocytosis more than NPs with BaP but less than MPs with BaP (Fig. 5A–C).

Lysosomal acid phosphatase (AcP) activity. AcP activity increased in hemocytes exposed to the highest concentrations of NPs and MPs alone and in cells exposed to the highest concentrations of 0.05 μm NPs and 4.5 μm MPs with BaP (Fig. 6A–C). AcP activity was especially induced in exposures to 4.5 μm MPs at 10^8 part./mL alone and with BaP (Fig. 6C). Comparing treatments with NPs and MPs alone or with BaP, AcP activity was significantly higher in exposure to 0.5 μm MPs alone compared to 0.5 μm MPs with BaP (Fig. 6B) but lower in hemocytes treated with 4.5 μm MPs alone compared to 4.5 μm MPs with BaP (Fig. 6C). BaP did not affect AcP activity at any concentration tested (Fig. 6). At equivalent concentrations of BaP, AcP activity was higher in hemocytes treated with NPs and MPs with BaP than in cells treated with BaP alone (Fig. 6A–C).

Reactive oxygen species (ROS) production. Exposures to NPs or MPs alone did not induce ROS production in mussel hemocytes compared to controls, but when combined with BaP, NPs and MPs induced ROS produc-




Figure 3. Cell viability (MTT assay) of mussel hemocytes exposed for 24 h to (A) 0.05 μm NPs, (B) 0.5 μm MPs and (C) 4.5 μm MPs alone or in combination with BaP and to BaP alone. Data are given as percentages with respect to control ± SD (n = 18). * indicates significant differences with respect to controls, # indicates significant differences between NPs/MPs with or without BaP and \$ indicates significant differences between NPs/MPs with BaP and BaP alone.

tion at the highest concentrations tested with respect to controls (Fig. 7A–C). BaP alone significantly increased ROS production at the three concentrations tested (Fig. 7A–C). At equivalent concentration of BaP, BaP alone induced a higher ROS production than 0.05 μm NPs with BaP (Fig. 7A).

Comet assay. NPs and MPs alone or with BaP produced significantly more DNA strand breaks at all concentrations tested compared to controls (Fig. 8). NPs and MPs with BaP were significantly more genotoxic than NPs




Figure 4. Plasma membrane integrity in mussel hemocytes exposed for 24 h to (A) 0.05 μm NPs, (B) 0.5 μm MPs and (C) 4.5 μm MPs alone or in combination with BaP and to BaP alone. Data are given as percentages with respect to control \pm SD ($n = 18$). * indicates significant differences with respect to controls, \$ indicates significant differences between NPs/MPs with BaP and BaP alone.

and MPs alone (Fig. 8). BaP was genotoxic at the three concentrations tested (Fig. 8). At the highest concentration tested (1 μM), BaP was almost as genotoxic as the positive control (100 μM H_2O_2) (Fig. 8). At equivalent BaP concentrations, BaP alone induced similar levels of DNA damage as NPs and MPs with BaP (Fig. 8).

Discussion

In this work we evaluated the ability of polystyrene (PS) NPs (0.05 μm) and MPs (0.5 μm and 4.5 μm) to transfer BaP to mussel hemocytes and to induce toxic effects in vitro. First, particles behaviour was characterized in different media and then, cells were exposed to a range of concentrations of NPs and MPs alone or with BaP in order to assess their intracellular fate and toxicity. Selected concentrations included those considered environmentally realistic²⁹. Cells were also exposed to BaP at 1 μM , 0.56 μM and 0.12 μM , which correspond to the concentrations




Figure 5. Phagocytic activity in mussel hemocytes exposed for 24 h to (A) 0.05 μm NPs, (B) 0.5 μm MPs and (C) 4.5 μm MPs alone or in combination with BaP and to BaP alone. Data are given as percentages with respect to control \pm SD ($n=18$). * indicates significant differences with respect to controls, # indicates significant differences between NPs/MPs with or without BaP and \$ indicates significant differences between NPs/MPs with BaP and BaP alone.

of BaP present in 10^{12} part./mL of 0.05 μm NPs with BaP and the concentrations of BaP adsorbed to 10^9 part./mL of 0.5 μm MPs and to 10^8 part./mL of 4.5 μm MPs with adsorbed BaP, respectively³⁵.

Regarding particles behaviour in suspension, results showed that particle aggregation occurred depending on the size of the particles, the suspension media and the presence of BaP. When suspended in the BME cell culture medium, 0.05 μm NPs alone or with BaP aggregated largely reaching 4.8 to 7.7 μm , while MPs of 0.5 μm aggregated mostly in suspensions without BaP reaching up to 2 μm and MPs of 4.5 μm alone or with BaP did not aggregate. As already reported by other authors in different exposure media^{16,17,36–38}, smaller PS particles are




Figure 6. Lysosomal AcP activity in mussel hemocytes exposed for 24 h to **(A)** 0.05 µm NPs, **(B)** 0.5 µm MPs and **(C)** 4.5 µm MPs alone or in combination with BaP and to BaP alone. Data are given as percentages with respect to control \pm SD (n = 18). * indicates significant differences with respect to controls, # indicates significant differences between NPs/MPs with or without BaP and \$ indicates significant differences between NPs/MPs with BaP and BaP alone.

generally more prone to aggregation than larger ones. Song et al.³⁷ reported that larger PS MPs-COOH (200 nm) have higher stability than smaller PS NPs-COOH (50 nm) in CaCl₂ solution. Similarly, Dong et al.³⁶ reported that smaller PS MPs (0.1–0.6 µm) aggregated more rapidly than larger ones (0.8–1.5 µm) in seawater. The use of physiologically relevant media such as filtered serum of mussel hemolymph does not prevent aggregation of NPs and MPs^{16,17} while it can add variability in exposure conditions compared to the use of a standard medium with known composition such as BME. In spite of DLS results indicating a substantial aggregation in BME, especially in case of NPs, individual particles of 0.05, 0.5 and 4.5 µm were identified by TEM within the cells exposed to




Figure 7. ROS production in mussel hemocytes exposed for 24 h to (A) 0.05 μm NPs, (B) 0.5 μm MPs and (C) 4.5 μm MPs alone or in combination with BaP, to BaP alone and to 100 μM H₂O₂ (positive control). Data are given as percentages with respect to control \pm SD (n = 18). * indicates significant differences with respect to controls, # indicates significant differences between NPs/MPs with or without BaP and \$ indicates significant differences between NPs/MPs with BaP and BaP alone.

the respective NPs or MPs. This appears to suggest that particles interacted with cells plasma membrane and became internalized individually, as discussed later.

Comparing particle stability in the two media, aggregation was lower in DW than in BME, possibly due to the higher ionic strength of the latter. As defined by the Derjaguin-Landau-Verwey-Overbeek (DLVO) theory, the colloidal stability of particles depends on the balance between the repulsive electrical double layer forces and the attractive van der Waals force. In salty media, van der Waals interaction dominates as the effective repulsion




Figure 8. DNA damage in mussel hemocytes exposed for 24 h to 0.05 μm NPs, 0.5 μm MPs and 4.5 μm MPs alone or in combination with BaP, to BaP alone and to 100 μM H_2O_2 (positive control). Data are given as % DNA in tail \pm SD ($n = 100$). * indicates significant differences with respect to controls, # indicates significant differences between NPs/MPs alone or with BaP.

between NPs or MPs decreases by the increased concentration of electrolytes³⁹. Thus, the high salt concentrations present in the BME increased the rate of aggregation of NPs and MPs resulting in decreased particles stability. On the other hand, aggregation was lower in particles with associated BaP. It has been reported that the presence of organic matter may increase particles stability³⁸. Organic molecules bind to the particle surface via adsorption or hydrophobic interaction, increasing the steric and electrostatic repulsion between particles thus reducing aggregation³⁹.

As to surface charge, NPs and MPs alone or with BaP showed a consistent negative surface charge, with Z potential values varying from -10.1 to -53.7 mV, in line with results in other exposure media^{16,17}. MPs of 4.5 μm alone or with BaP showed higher absolute Z potential values in DW compared to suspensions in BME, thus exhibiting a higher stability in the former. Conversely, particles of 0.05 and 0.5 μm showed lower absolute Z potential values in DW compared to BME, indicating that, for small particles, the greater surface to volume ratio may favour the adsorption of medium components (eg. amino acids, vitamins) promoting a higher particle stability⁴⁰.

Particle properties such as surface charge, shape and size as well as the cell type are main determinants of uptake mechanisms and intracellular fate of NPs and MPs⁴¹. According to TEM analysis, NPs were found inside membrane-bound vesicles, especially within large tertiary lysosomes or residual bodies containing lipofuscins, which were more abundant than in control cells. This might indicate involvement of endocytic mechanisms and also of autophagy, as increased lipofuscin in mussel digestive cells is indicative of oxidative cell injury and autophagic dysfunction⁴². Nanoparticles have been suggested to either induce the process of autophagy or cause its dysfunction⁴³. NPs were also found free in the cytosol, which is consistent with their internalization through diffusion across the plasma membrane, although it could also indicate that they escaped from the endo-lysosomal system after internalization⁴³. MPs of 0.5 μm were found extracellularly surrounded by cytoplasmic projections and intracellularly within membrane-bound vesicles suggesting internalization via macropinocytosis although other endocytic pathways could also be involved⁴³. Finally, MPs of 4.5 μm appeared to enter in the hemocytes by phagocytosis and were found inside vesicles resembling phagosomes or phagolysosomes⁴⁴, in line with results of confocal microscopy. As in exposures to NPs, cells exposed to both sizes of MPs showed an increased amount of residual bodies and lipofuscins indicative of enhanced lysosomal and autophagic activity. Overall, as summarized in Fig. 9, our results agree well with studies indicating that NPs (0.05 μm or less) can be internalized by ATP-independent passive transport or endocytic mechanisms^{41,43,45,46}, while small MPs (0.5 μm or less) can be internalized through clathrin or caveolae-mediated endocytic pathways or via macropinocytosis, and larger MPs (approximately 1 μm or larger) are taken up by phagocytosis^{17,44,47–50}.

Confocal microscopy allowed to determine the intracellular fate of BaP in cells exposed to NPs with BaP and in cells exposed to MPs with adsorbed BaP, following Batel et al.⁵¹. Our results showed that PS NPs and MPs may act as Trojan horse carriers of BaP into mussel hemocytes. BaP fluorescence partly co-localized with labelled lysosomes, that could correspond to BaP associated to plastic particles incorporated by the different endocytic uptake routes mentioned before. BaP was also found outside of lysosomes, possibly due to entry of particles by diffusion or other non-endocytic mechanisms or by escaping the endo-lysosomal system after entry, as mentioned before. In exposures to BaP alone, BaP was found throughout the cell, mainly internalized into lysosomes, as shown before in mussel digestive cells upon exposure of mussels to BaP⁴². As far as we know, there are no previous studies on the intracellular localization of BaP or other PAHs associated to NPs or MPs. As to the localization of NPs or MPs alone, studies on human cells showed that PS NPs⁵² and PS MPs of 500 nm or less^{53,54} accumulated in the cytosol and inside lysosomes whereas larger PS particles (5 μm) accumulated mainly inside lysosomes⁵⁴. In oyster hepatopancreas cells, Gaspar et al.¹⁵ reported that 50 nm PS NPs accumulated inside lysosomes and endosomes. In mussel hemocytes, PS particles of 50 nm, 100 nm and 1 μm were mostly co-localized




Figure 9. Simplified schematic diagram of a model for uptake and trafficking of PS NPs and MPs in mussel hemocytes. NPs formed large aggregates in the BME culture medium but were internalized and found in the cytosol and inside membrane-bound vesicles, indicating possible entrance by passive diffusion and endocytic processes, respectively. Also, it could be that NPs found in the cytosol escaped from the endo-lysosomal system after internalization (?). MPs of 0.5 μm were found extracellularly surrounded by cytoplasmic projections and intracellularly within membrane-bound vesicles suggesting internalization via macropinocytosis although other endocytic pathways could also be involved. NPs and MPs of 0.5 μm could reach the endosomes and endolysosomes. Finally, MPs of 4.5 μm appeared to enter in the hemocytes by phagocytosis and were found inside vesicles resembling phagosomes or phagolysosomes. Both by autophagic or heterophagic pathways, the final fate of NPs and MPs could be large tertiary lysosomes or residual bodies containing lipofuscins, which were more abundant than in control cells. It could be that these residual bodies were exocytosed from the cells at a later stage.

with lysosomes except for 50 nm NPs that were also found in the cytoplasm outside lysosomes¹⁷. Our results of confocal microscopy are in accordance with these findings and also with TEM results.

Once inside the cells, both plastic particles and associated BaP could cause an array of toxic effects. Effects of NPs and MPs alone on cell viability (MTT assay) occurred only at relatively high concentrations²⁹. Thus, cell viability decreased significantly upon exposures to 10^{12} part./mL (50 $\mu\text{g}/\text{mL}$) of 0.05 μm PS NPs; 10^9 part./mL (50 $\mu\text{g}/\text{mL}$) of 0.5 μm PS MPs and 10^6 part./mL (50 $\mu\text{g}/\text{mL}$) and 10^8 part./mL (5000 $\mu\text{g}/\text{mL}$) of 4.5 μm PS MPs. In accordance with our results, other authors also reported low cytotoxicity of PS NPs and MPs in different cell models *in vitro*^{21,54,55}. For the three sizes of particles tested cytotoxicity occurred at PS concentrations of 50 $\mu\text{g}/\text{mL}$ or higher. Comparing the cytotoxicity of the three sizes of particles at the same PS mass concentration of 50 $\mu\text{g}/\text{mL}$, 0.05 μm NPs were more toxic (47.16% decrease of cell viability) than 0.5 μm and 4.5 μm MPs (23.35% and 29.67% decrease of cell viability, respectively). Results agree with the idea that smaller particles show higher bioreactivity due to their higher surface to volume ratio compared to larger particles⁵⁶. Hwang et al.⁵⁷ reported that smaller PP MPs (20 μm) were more toxic than larger ones (25–200 μm) to murine immune cells. Similarly, Stock et al.⁵⁵ reported that smaller PS MPs (1 μm) exerted higher cytotoxicity than larger PS MPs (4 and 10 μm) to Caco-2 cells.

In cells treated with NPs or MPs with BaP, cytotoxicity was higher than in cells exposed to PS particles alone. BaP alone was cytotoxic to hemocytes only at the highest concentration tested (1 μM , the same concentration present in 10^{12} part./mL of 0.05 μm NPs). Previous studies *in vitro* have already reported the cytotoxicity of BaP in mussel hemocytes^{58,59}. In mussels exposed *in vivo* to the same PS MPs used in this work (0.5 and 4.5 μm) alone or with BaP, González-Soto et al.²² reported larger effects on cell viability and catalase activity in hemocytes from mussels exposed to MPs with BaP compared to animals exposed to MPs alone. Similarly, other studies *in vivo* with mussels have also reported significant effects of MPs with PAHs in hemocytes^{31,32}. In the human cell line A549 exposed *in vitro* to 190 nm PS MPs alone or with BaP and to BaP alone, PS MPs with BaP were more toxic than MPs or BaP alone⁶⁰. Thus, the increased cytotoxicity of PS particles with BaP to mussel hemocytes appeared to be due to the presence of BaP carried into the cells, as demonstrated by confocal microscopy.

Similar to results on cell viability, plasma membrane integrity decreased significantly only at high concentrations of exposure to plastic particles, e.g., 10^{12} part./mL (50 $\mu\text{g}/\text{mL}$) of 0.05 μm NPs, 10^6 , 10^8 and 10^9 part./mL (0.5 to 50 $\mu\text{g}/\text{mL}$) of 0.5 μm MPs and 10^8 part./mL (5000 $\mu\text{g}/\text{mL}$) of 4.5 μm MPs. Similarly, comparing the effects of the three sizes of particles at the same PS mass, smaller NPs and MPs exerted a higher impact on plasma membrane integrity than 4.5 μm MPs. Rossi et al.⁶¹ used molecular simulations to determine the effect of PS

particles on model biological membranes and found that PS particles severely affected membrane organization and integrity especially at high concentrations. BaP alone significantly reduced plasma membrane integrity at the three concentrations tested. BaP is known to react with phospholipid membranes causing swelling and expansion, altering the structure and functionality of the membranes and compromising their integrity⁶². Comparing effects of plastic particles with associated BaP to effects of BaP alone at equivalent concentrations, no significant differences were seen for 0.5 μm MPs whereas plasma membrane integrity was reduced in BaP alone compared to NPs with BaP but increased in BaP alone compared to 4.5 μm MPs with adsorbed BaP. This might indicate a higher impact of larger 4.5 μm plastic particles on plasma membrane integrity compared to BaP effect.

Phagocytosis is the primary cellular defense reaction in invertebrate hemocytes and is first triggered by interaction of particles with cells plasma membrane. Mussel hemocytes, especially granulocytes, have long been known to actively phagocytose latex and zymosan particles *in vitro*⁴⁴. Our results showed that exposure to PS NPs and small 0.5 μm MPs alone induced hemocytes phagocytosis of zymosan particles, an immunostimulatory effect that is widely reported for mussel hemocytes exposed to other nanoscale particles^{63,64}. Importantly, for 0.5 μm MPs this effect occurred at the same concentrations with decreased plasma membrane integrity whereas for NPs the increase in zymosan phagocytosis occurred at concentrations that did not disturb plasma membrane integrity. On the other hand, hemocytes exposed to larger 4.5 μm MPs were not more active in zymosan phagocytosis than controls possibly because they were already loaded with MP particles, as seen by TEM. Studies on LDPE MPs reported an increase of hemocytes phagocytosis³², however other *in vivo* studies on PS and PE particles in the range 100–1000 μm ³¹ or *in vitro* studies on amino modified 50 nm PS NPs¹⁸ or fluorescent 1 μm MPs¹⁶ reported the opposite. Surface characteristics of NPs and MPs such as the presence of functional groups and surface charge and presence of a protein corona are decisive for particles recognition and internalization^{11,18}. Further, methods to measure phagocytic activity differ largely; while some studies have measured phagocytosis of plastic particles themselves using flow cytometry (e.g.,¹⁶) we studied here phagocytosis of zymosan in cells exposed to NPs and MPs.

Conversely to findings with PS particles alone, in cells exposed to PS NPs and MPs with BaP and to BaP alone phagocytic activity was reduced. This immune inhibitory effect was significant with respect to controls at highest concentrations tested for the three sizes of plastics with BaP but differences between plastics alone versus plastics with BaP were already significant at 10^2 part./mL of 0.05 μm NPs and 0.5 μm MPs. Reduced phagocytosis could be due to a shift in the recognition of the PS particles caused by the presence of BaP on the surface of particles. Since phagocytic activity requires an intact and functional actin cytoskeleton⁶⁵, another possible explanation could be that BaP affected the integrity of the actin cytoskeleton of mussel hemocytes^{58,59} thus reducing phagocytosis of zymosan. Therefore, phagocytosis results suggest not only a carrier or Trojan horse effect of NPs and MPs but also a differential modulation of immune response in hemocytes caused by PS particles and BaP.

The uptake and trafficking of NPs and MPs at high concentrations along the endo-lysosomal system of hemocytes as well as the increased lysosomal and autophagic activities observed by TEM can be related to increased activities of lysosomal acid hydrolases. In agreement, AcP activity increased significantly in hemocytes exposed to the highest concentrations of 0.05 μm NPs (10^{12} part./mL or 50 $\mu\text{g}/\text{mL}$) alone or with BaP, 0.5 μm MPs (10^9 part./mL or 50 $\mu\text{g}/\text{mL}$) alone, and 4.5 μm MPs (10^8 part./mL, 5000 $\mu\text{g}/\text{mL}$) alone or with BaP. As for other endpoints, smaller NPs and MPs were more effective than 4.5 μm MPs in inducing AcP activity when compared at the same PS mass. On the other hand, exposure to BaP alone did not affect AcP activity in hemocytes thus indicating that AcP induction was mainly caused by PS particles and not by BaP. Sendra et al.¹⁶ also found increased tracking of lysosomes by flow cytometry in mussel granular hemocytes exposed for 3 h to PS particles of 0.1 and 1 μm *in vitro*. In an *in vivo* study, Revel et al.⁶⁶ reported an enhancement of hemocytes AcP activity in mussels exposed to low and medium concentrations (0.008 and 10 $\mu\text{g}/\text{L}$) of a polydispersed mixture of PE MPs (0.4 to 720 μm) and PP MPs (0.4 to 950 μm). In another study *in vivo*, Avio et al.³¹ reported an up-regulation of different genes coding for lysosomal enzymes in mussels exposed to 50 $\mu\text{g}/\text{L}$ of PE and PS MPs (100 to 1000 μm) alone and with pyrene. As mentioned before, the enhancement in AcP activity could be related to the increased endo-lysosomal activity upon exposure to PS NPs and MPs but it could also be due to an hypersynthesis of AcP and activation of cellular defenses as AcP is secreted as a humoral defense factor in mussel hemocytes⁶⁷.

Exposure to PS particles alone did not induce intracellular ROS production in hemocytes at any concentration tested. Similar results were obtained in fish leucocytes exposed *in vitro* to PVC-PE MPs⁶⁸. In murine immunocytes, Hwang et al.⁵⁷ reported that PP MPs increased ROS production only at the highest concentration (1000 $\mu\text{g}/\text{mL}$). However, Wu et al.⁵⁴ reported that PS MPs at 200 $\mu\text{g}/\text{mL}$ significantly increased intracellular ROS production in the human Caco-2 cell line. In mussel hemocytes exposed to amino modified 50 nm PS NPs extracellular ROS levels increased significantly¹⁸ whereas a complex ROS response pattern was found by Sendra et al.¹⁶ for different subpopulations of mussel hemocytes and different PS plastic sizes. In our study, it could be that intracellular ROS production did not increase in hemocytes exposed to high concentrations of PS particles because these concentrations were cytotoxic to the cells. Another possible explanation could be that ROS production increased earlier than at 24 h, as shown by Sendra et al.¹⁶, and triggered antioxidant mechanisms which then reduced ROS levels at the 24 h time point. In support of this idea, in mussel hemocytes exposed *in vitro* to CdS quantum dots, intracellular ROS production significantly increased already at 1 h and then dropped up to 24 h⁶³. In fact, the TEM finding that exposures to high concentrations of NPs and MPs caused an increase in residual bodies containing highly oxidized lipofuscin materials point to an oxidative stress situation as well as to enhanced lysosomal and autophagic activities⁴².

In cells exposed to PS NPs and MPs with BaP, ROS production increased at the highest concentrations tested for the three particle sizes. Exposure to BaP alone also enhanced ROS production in hemocytes at all three concentrations tested, in agreement with previous data in hemocytes *in vitro*^{58,59} and in mussels *in vivo*⁶⁹. Intracellular ROS production is a consequence of the generation of reactive metabolites during BaP biotransformation, such as BaP diol epoxide, which is known to bind covalently to DNA, and BaP quinones which induce oxidative

stress^{70,71}. It has already been reported that exposure of bivalves *in vivo* to MPs with BaP may cause an increase in ROS production²³ or in antioxidant catalase activity²². Therefore, our results suggest that the increase in ROS production in hemocytes exposed to high concentrations of PS NPs and MPs with BaP was mainly caused by BaP, confirming again that PS NPs and MPs acted as carriers of BaP to mussel hemocytes.

Partly due to ROS overproduction, BaP is a well-known genotoxic and carcinogenic agent and its ability to cause DNA strand breaks has been widely reported in bivalve species^{69,72}. In agreement, in this study BaP alone was genotoxic at all concentrations tested, showing a dose-dependent response. Further, DNA damage significantly increased in cells treated with NPs and MPs alone or with BaP at the two concentrations tested for each PS particle size. Results showed higher levels of DNA damage in cells treated with NPs and MPs with BaP compared to cells treated with PS particles alone. Similar levels of DNA damage were observed in cells treated with BaP alone and in cells treated with NPs or MPs with BaP at equivalent BaP concentrations, indicating that BaP was the main inducer of genotoxicity. Recent studies have reported the capacity of MPs alone or with PAHs to induce genotoxicity in bivalves *in vivo*^{22,66,73,74}. The mechanisms leading to genotoxicity of NPs and MPs are still not fully understood but seem to be related to increased ROS production and oxidative stress⁷³. As discussed before, in this study NPs and MPs alone did not induce ROS production after 24 h exposure, however an earlier induction might have occurred, leading to development of genotoxic effects.

Conclusions

Taken together our results indicate that PS particle size, ionic strength of the medium and presence of BaP were relevant factors influencing PS particle stability. Despite PS particles, and especially 0.05 μm NPs, largely aggregated in BME culture medium, individual particles of 0.05, 0.5 and 4.5 μm were identified within the cells exposed to the respective NPs or MPs. Cells appeared to internalize PS NPs and MPs alone or with BaP via different mechanisms depending on their size, and once in the cells, particles were found especially in large lysosomes containing lipofuscins, which were more abundant in cells exposed to PS particles, and also in the cytoplasm outside lysosomes. Results on the toxicity tests showed that PS particles alone or with BaP were cytotoxic (MTT assay) to hemocytes only at the highest concentrations tested. The same occurred for most sublethal endpoints determined except for increased phagocytic activity provoked by NPs and 0.5 μm MPs at lower concentrations. In general, at the same PS mass, smaller NPs and MPs exerted a higher toxicity compared to larger 4.5 μm MPs. Virgin PS NPs and MPs caused damage to the plasma membrane integrity, increased phagocytic and acid phosphatase activities and induced DNA damage. PS NPs and MPs with BaP decreased plasma membrane integrity and phagocytic activity, increased lysosomal AcP activity and induced intracellular ROS production and genotoxicity. Similar effects were observed in cells exposed to BaP alone. Overall, plastic particles appeared to be the main drivers for reduced plasma membrane integrity and increased phagocytic and lysosomal activities in hemocytes whereas BaP appeared to contribute more to reduced cell viability, inhibition of phagocytosis and induced ROS production and genotoxicity.

In this work we used PS NP and MP spheres as model materials to study their fate and toxicity in mussel cells but other environmentally relevant polymers and shapes need to be studied in the future for a comprehensive understanding of the risks posed by NP and MP pollution in the marine environment. For instance, PP and PE were the predominant polymers in bivalves and sediments in the Bay of Biscay (north-east of the Atlantic Ocean) and fragments were the most common MP type, followed by fibres (reviewed in Mendoza et al.³). Also weathering (aging) and biofilm formation in environmental plastics are important factors to take into consideration in future toxicological studies. Studies need to be conducted at environmentally realistic concentrations even though actual exposure levels and levels of MPs accumulated in biota are possibly underestimated⁸. As to the selected biological model, mussel hemocytes represent the most important front of immune defense in bivalves and also a suitable rapid screening tool for toxicity profiling and for mechanistic understanding of the mode of action of NPs and MPs and associated pollutants. Current conclusions drawn on the Trojan horse ability of NPs and MPs for BaP using this *in vitro* model agree well with *in vivo* studies^{22,23,32}, pointing out to their potential use as predictive tools in environmental risk assessment. Finally, the fact that PS NPs and MPs can act as carriers of BaP to mussel cells and that presence of BaP enhanced the toxicity of PS particles, rise concerns about the risks posed by nano and microplastics in association with POPs to aquatic organisms.

Methods

Preparation of NPs and MPs with BaP. The plastic particles selected for the experiments were unlabelled polystyrene (PS) particles of three different sizes: nanoplastics (NPs) of 0.05 μm (Polysciences Inc., cat.# 08,691) and microplastics (MPs) of 0.5 and 4.5 μm (Polysciences Inc., cat.# 07,307 and cat.# 17,135, respectively). PS NPs and MPs were delivered at room temperature and stored at 4 °C.

MPs with sorbed BaP were prepared according to Batel et al.⁵¹ with modifications explained below. 0.5 μm MPs (10^9 part./mL) and 4.5 μm MPs (10^8 part./mL) were mixed with 1 μM BaP prepared in 0.001% DMSO in distilled water and left in agitation for 24 h in darkness in order to promote BaP sorption to the MPs. After that, suspensions were filtered (0.2 μm pore size) and retained MPs with sorbed BaP were recovered by passing cell culture media (Basal Medium Eagle (BME) supplemented with 1% gentamicin, 1040 mOsm/kg, pH 7.4) through the opposite side of syringe filters. As filtering and recovery of NPs was not possible due to their nanosize, 0.05 μm NPs (10^{12} part./mL) were directly mixed with 1 μM BaP prepared in 0.001% DMSO in supplemented BME and left in agitation for 24 h in darkness prior to the exposures. As previously reported by other authors^{22,59,75} DMSO at 0.001% is not cytotoxic to mussel cells. All suspensions were prepared in glass vials wrapped in aluminium foil.

Characterization of NPs and MPs alone or with BaP in different media. Hydrodynamic size and surface charge of 0.05 μm NPs (10^{12} part./mL), 0.5 μm MPs (10^9 part./mL) and 4.5 μm MPs (10^8 part./mL) with

or without BaP suspended in distilled water and in supplemented BME were assessed by DLS (Dynamic Light Scattering, Malvern Zetasizer Nano ZS, Malvern Instruments Ltd, Worcestershire, UK). 0.05 μm NPs with BaP were characterized only in BME because they were directly mixed with BaP and BME during the preparation procedure. Three measurements were done for each particle in each different media.

Hemocytes primary culture and in vitro exposures. Mussels, *Mytilus galloprovincialis* (3.5–4.5 cm shell length) were collected in Plentzia, Bay of Biscay (43° 24' 41.9" N 2° 57' 01.1" W), a relatively clean site⁷⁶. Animals were acclimatized for 2 days in aerated tanks with seawater (0.5 L/mussel at 18 °C), daily food supply (Marin Coraliquid Sera GmbH, Heinsberg, Germany) and 12 h photoperiod in the aquaria facility of the Cell Biology in Environmental Toxicology research group (CBET, UPV/EHU).

After acclimatization, hemolymph was withdrawn from mussel's posterior adductor muscle under aseptic conditions in a vertical laminar airflow cabinet (Cultair BC100, Cultek S.L., Madrid, Spain). Hemolymph from 50 animals was pooled and diluted 9:1 in anti-aggregation solution (171 mM NaCl; 0.2 M Tris; 0.15% v/v HCl 1 N; 24 mM EDTA) to obtain 1×10^6 cells/mL, >95% viable according to trypan blue exclusion assay⁷⁶. Cell suspensions were seeded into μ -Dish 35 mm glass-bottom petri dishes (Ibidi GmbH, Planegg, Germany) for confocal studies, into 96-well microplates for TEM studies or into glass-coated 96-well microplates for the toxicity assays. 96-well microplates were centrifuged (Beckman Coulter, Palo Alto, USA) at 270 g for 10 min at 4 °C in order to favour cells to attach. Cells were kept in culture media (Basal Medium Eagle 1040 mOsm/kg, pH 7.4, supplemented with 0.001% gentamicin) for 24 h at 18 °C in a Sanyo incubator (Osaka, Japan) to establish the primary cell cultures before performing the exposures.

For the intracellular localization studies, hemocytes were exposed for 24 h to 0.05 μm NPs (10^{12} part./mL), 0.5 μm MPs (10^9 part./mL) and 4.5 μm MPs (10^8 part./mL) alone or with BaP and to BaP (1 μM). For the toxicity assays, cells were exposed for 24 h to 0.05 μm NPs (10^2 , 10^3 , 10^5 , 10^6 , 10^8 , 10^9 and 10^{12} part./mL), 0.5 μm MPs (10^2 , 10^3 , 10^5 , 10^6 , 10^8 and 10^9 part./mL) and 4.5 μm MPs (10^2 , 10^3 , 10^5 , 10^6 and 10^8 part./mL) alone or with BaP. These ranges of concentrations were selected to allow comparisons in terms of number of particles (10^2 to 10^8 part./mL of NPs or MPs) and in terms of mass of PS (10^9 part./mL of 0.05 μm NPs = 10^6 part./mL of 0.5 μm MPs = 10^3 part./mL of 4.5 μm MPs correspond to 0.05 μg PS/mL and 10^{12} part./mL of 0.05 μm NPs = 10^9 part./mL of 0.5 μm MPs = 10^6 part./mL of 4.5 μm MPs correspond to 50 μg PS/mL). For the genotoxicity assessment (Comet Assay), cells were exposed for 24 h to 0.05 μm NPs (10^8 and 10^{12} particles/mL), 0.5 μm MPs (10^8 and 10^9 part./mL) and 4.5 μm MPs (10^6 and 10^8 part./mL) alone or with BaP. In parallel, cells were exposed to BaP at 1 μM , 0.56 μM and 0.12 μM , which are the concentrations of BaP present in 10^{12} part./mL of 0.05 μm NPs with BaP and the concentrations of BaP adsorbed to 10^9 part./mL of 0.5 μm MPs and 10^8 part./mL of 4.5 μm MPs with adsorbed BaP respectively, according to Martínez-Álvarez et al.³⁵. Cells kept in supplemented BME were used as negative controls.

Intracellular fate of NPs and MPs alone or with BaP. Intracellular fate of NPs and MPs was assessed by transmission electron microscopy (TEM) and confocal fluorescence microscopy. For TEM analysis⁷⁷, after exposures hemocytes were washed 3 times with PBS and detached from the microplates using trypsin/EDTA until cells rounded up, transferred to microtubes containing cell culture media and centrifuged at 270 g for 10 min at 4 °C. Afterwards, supernatants were removed and pellets were fixed in filtered seawater containing 2.5% glutaraldehyde at 4 °C for 1 h. Then, samples were postfixed with osmium tetroxide and ferrocyanide (1:1), cleaned in filtered seawater, dehydrated in an ethanol series and embedded in Epon. Ultrathin (70 nm) sections were cut in a Reichert-Jung Ultracut E ultramicrotome (Leica Microsystems; Wetzlar, Germany) and mounted on Cu grids coated with Formvar (Sigma Aldrich, St. Louis, USA). TEM imaging was performed on a high resolution JEOL 2000 microscope (JEOL Co., Tokyo, Japan) operated at 80 kV.

For confocal microscopy, after exposures cells were washed three times with PBS in order to eliminate PS particles and then hemocytes' lysosomes were labelled with LysoTracker™ Deep Red (ThermoFisher, Waltham, USA) according to manufacturer's instructions. Cells were analyzed in brightfield and fluorescence emitted by the labelled lysosomes was detected at $\lambda_{\text{excitation}}$ 647/ $\lambda_{\text{emission}}$ 668 nm whereas fluorescence corresponding to the BaP aromatic rings was detected at $\lambda_{\text{excitation}}$ 340/ $\lambda_{\text{emission}}$ 488 nm⁵¹. Images were merged and edited using the software ImageJ FIJI (National Institutes of Health, USA).

In vitro toxicity assays. In vitro toxicity assays were carried out as described previously^{63,77}. Cell viability was assessed using the MTT assay (Sigma-Aldrich, St. Louis, USA) and absorbance was read at 570 nm in a Biotek EL 312 microplate reader (Winooski, USA). Plasma membrane integrity was assessed using the 5-carboxyfluorescein diacetate acetoxyethyl ester (CFDA-AM) assay and fluorescence was measured at $\lambda_{\text{excitation}}$ 485/ $\lambda_{\text{emission}}$ 535 nm in a Bio-Tek FLx 800 microplate reader (Winooski, USA). Phagocytic activity was measured in the same absorbance microplate reader mentioned before at 550 nm. Lysosomal acid phosphatase (AcP) activity was quantified in the same absorbance microplate reader at 405 nm. Reactive oxygen species (ROS) production was detected using the Carboxy-H₂DCFDA assay (ThermoFisher, Waltham, USA) and fluorescence was measured at $\lambda_{\text{excitation}}$ 492–495/ $\lambda_{\text{emission}}$ 517–527 nm in the same fluorescence microplate reader mentioned before. Comet assay was performed as detailed before⁶³ with the following modifications. Slides were stained with 1% GreenSafe Premium (NZYTech, Lisbon, Portugal) and observed under an Olympus BX61 fluorescence microscope (Olympus optical Co, Hamburg, Germany). 100 randomly selected cells were analyzed and scored using the OpenComet tool of the software ImageJ FIJI. Cells treated with hydrogen peroxide (100 μM) were used as positive controls for the ROS and Comet assays. All assays were repeated three times and in each case there were 6 replicates per experimental group.

Differences between control cells and cells exposed to different concentrations of the NP or MP treatments were analyzed through the Kruskal–Wallis test followed by the Dunn's post-hoc test for multiple comparisons. Differences between treatments with or without BaP, at the same NP or MP concentration, were evaluated through the Mann–Whitney's U test. Mann–Whitney's U test was also used to compare responses obtained in cells treated with BaP with cells treated with NPs or MPs with BaP at the same BaP concentration. Significant differences were established at $p < 0.05$ in all cases. All statistical analyses were carried out using the SPSS statistical software (IBM SPSS Statistics 23, Chicago, USA).

Data availability

The source data underlying Figures, Table and Supplementary Information are available from the authors upon request.

Received: 31 May 2021; Accepted: 12 October 2021

Published online: 17 November 2021

References

1. PlasticOceans. *Plastic Pollution Facts*. <https://plasticoceans.org/the-facts/> (2020).
2. Barnes, D. K. A., Galgani, F., Thompson, R. C. & Barlaz, M. Accumulation and fragmentation of plastic debris in global environments. *Philos. Trans. R. Soc. Lond., B, Biol. Sci.* **364**, 1985–1998 (2009).
3. Mendoza, A. *et al.* Microplastics in the Bay of Biscay: An overview. *Mar. Pollut. Bull.* **153**, 110996 (2020).
4. Andrady, A. L. Microplastics in the marine environment. *Mar. Pollut. Bull.* **62**, 1596–1605 (2011).
5. Koelmans, A. A., Besseling, E. & Shim, W. J. Nanoplastics in the aquatic environment. In *Critical Review in Marine Anthropogenic Litter* (eds Bergmann, N. *et al.*) 325–340 (SpringerLink, 2015).
6. Frias, J. P. G. L. & Nash, R. Microplastics: Finding a consensus on the definition. *Mar. Pollut. Bull.* **138**, 145–147 (2019).
7. Peng, L. *et al.* Micro- and nano-plastics in marine environment: Source, distribution and threats—A review. *Sci. Total Environ.* **698**, 134254 (2020).
8. Ribeiro, F. *et al.* Out of sight but not out of mind: Size fractionation of plastics bioaccumulated by field deployed oysters. *J. Hazard. Mater.* **2**, 100021 (2021).
9. Wright, S. L., Thompson, R. C. & Galloway, T. S. The physical impacts of microplastics on marine organisms: A review. *Environ. Pollut.* **178**, 483–492 (2013).
10. Wang, J., Tan, Z., Peng, J., Qiu, Q. & Li, M. The behaviors of microplastics in the marine environment. *Mar. Environ. Res.* **113**, 7–17 (2016).
11. Galloway, T. S., Cole, M. & Lewis, C. Interactions of microplastic debris throughout the marine ecosystem. *Nat. Ecol. Evol.* **1**, 1–8 (2017).
12. Franzellitti, S., Canesi, L., Auguste, M., Wathsala, R. H. G. R. & Fabbri, E. Microplastic exposure and effects in aquatic organisms: A physiological perspective. *Environ. Toxicol. Pharmacol.* **68**, 37–51 (2019).
13. Xu, S., Ma, J., Ji, R., Pan, K. & Miao, A. J. Microplastics in aquatic environments: Occurrence, accumulation, and biological effects. *Sci. Total Environ.* **703**, 134699 (2020).
14. Sussarellu, R. *et al.* Oyster reproduction is affected by exposure to polystyrene microplastics. *Proc. Nat. Acad. Sci. U. S. A.* **113**, 2430–2435 (2016).
15. Gaspar, T. R., Chi, R. J., Parrow, M. W. & Ringwood, A. H. Cellular bioreactivity of micro- and nano-plastic particles in oysters. *Front. Mar. Sci.* **5**, 1–8 (2018).
16. Sendra, M., Carrasco-Braganza, M. I., Yeste, P. M., Vila, M. & Blasco, J. Immunotoxicity of polystyrene nanoplastics in different hemocyte subpopulations of *Mytilus galloprovincialis*. *Sci. Rep.* **10**, 1–14 (2020).
17. Sendra, M. *et al.* Nanoplastics: From tissue accumulation to cell translocation into *Mytilus galloprovincialis* hemocytes. Resilience of immune cells exposed to nanoplastics and nanoplastics plus *Vibrio splendidus* combination. *J. Hazard. Mater.* **388**, 121788 (2020).
18. Canesi, L. *et al.* Evidence for immunomodulation and apoptotic processes induced by cationic polystyrene nanoparticles in the hemocytes of the marine bivalve *Mytilus*. *Mar. Environ. Res.* **111**, 34–40 (2015).
19. Paul-Pont, I. *et al.* Exposure of marine mussels *Mytilus spp.* to polystyrene microplastics: Toxicity and influence on fluoranthene bioaccumulation. *Environ. Pollut.* **216**, 724–737 (2016).
20. Capolupo, M., Franzellitti, S., Valbonesi, P., Lanzas, C. S. & Fabbri, E. Uptake and transcriptional effects of polystyrene microplastics in larval stages of the Mediterranean mussel *Mytilus galloprovincialis*. *Environ. Pollut.* **241**, 1038–1047 (2018).
21. González-Fernández, C. *et al.* Cellular responses of Pacific oyster (*Crassostrea gigas*) gametes exposed *in vitro* to polystyrene nanoparticles. *Chemosphere* **208**, 764–772 (2018).
22. González-Soto, N. *et al.* Impacts of dietary exposure to different sized polystyrene microplastics alone and with sorbed benzo[a]pyrene on biomarkers and whole organism responses in mussels *Mytilus galloprovincialis*. *Sci. Total Environ.* **684**, 548–566 (2019).
23. Tang, Y. *et al.* Immunotoxicity of microplastics and two persistent organic pollutants alone or in combination to a bivalve species. *Environ. Pollut.* **258**, 113845 (2020).
24. Gonçalves, J. M. & Bebianno, M. J. Nanoplastics impact on marine biota: A review. *Environ. Pollut.* **273**, 116426 (2021).
25. Ziccardi, L. M., Edginton, A., Hentz, K., Kulacki, K. J. & Driscoll, S. K. Microplastics as vectors for bioaccumulation of hydrophobic organic chemicals in the marine environment: A state-of-the-science review. *Environ. Toxicol. Chem.* **35**, 1667–1676 (2016).
26. Menéndez-Pedriz, A. & Jaumot, J. Interaction of environmental pollutants with microplastics: A critical review of sorption factors, bioaccumulation and ecotoxicological effects. *Toxics* **8**, 40 (2020).
27. Hirai, H. *et al.* Organic micropollutants in marine plastics debris from the open ocean and remote and urban beaches. *Mar. Pollut. Bull.* **62**, 1683–1692 (2011).
28. Camacho, M. *et al.* Organic pollutants in marine plastic debris from Canary Islands beaches. *Sci. Total Environ.* **662**, 22–31 (2019).
29. Rios-Mendoza, L. M. & Jones, P. R. Characterisation of microplastics and toxic chemicals extracted from microplastic samples from the North Pacific Gyre. *Environ. Chem.* **12**, 611–617 (2015).
30. Gorman, D. *et al.* Organic contamination of beached plastic pellets in the South Atlantic: Risk assessments can benefit by considering spatial gradients. *Chemosphere* **223**, 608–615 (2019).
31. Avio, C. G. *et al.* Pollutants bioavailability and toxicological risk from microplastics to marine mussels. *Environ. Pollut.* **198**, 211–222 (2015).
32. Pittura, L. *et al.* Microplastics as vehicles of environmental PAHs to marine organisms: Combined chemical and physical hazards to the Mediterranean mussels *Mytilus galloprovincialis*. *Front. Mar. Sci.* **5**, 103 (2018).
33. Magara, G. *et al.* Effects of combined exposures of fluoranthene and polyethylene or polyhydroxybutyrate microplastics on oxidative stress biomarkers in the blue mussel (*Mytilus edulis*). *J. Toxicol. Environ. Health A* **10**, 616–625 (2019).
34. Sun, S. *et al.* Immunotoxicity of petroleum hydrocarbons and microplastics alone or in combination to a bivalve species: Synergic impacts and potential toxication mechanisms. *Sci. Total Environ.* **728**, 138852 (2020).

35. Martínez-Álvarez, I. *et al.* Sorption of PAHs onto polystyrene microplastics depending on particle size. *Toxics*, submitted.
36. Dong, X., Sun, D., Liu, G., Cao, C. & Jiang, X. Aqueous foam stabilized by hydrophobically modified cellulose and alkyl polyoxyethyl sulfate complex in the presence and absence of electrolytes. *Colloids Surf. A* **345**, 58–64 (2009).
37. Song, Z. *et al.* Fate and transport of nanoplastics in complex natural aquifer media: Effect of particle size and surface functionalization. *Sci. Total Environ.* **669**, 120–128 (2019).
38. Wang, X. *et al.* A review of microplastics aggregation in aquatic environment: Influence factors, analytical methods, and environmental implications. *J. Hazard. Mater.* **402**, 123496 (2021).
39. Singh, N., Tiwari, E., Khandelwala, N. & Darbha, G. K. Understanding the stability of nanoplastics in aqueous environments: Effect of ionic strength, temperature, dissolved organic matter, clay, and heavy metals. *Environ. Sci.: Nano* **6**, 2968 (2019).
40. Liu, J. *et al.* Polystyrene nanoplastics-enhanced contaminant transport: Role of irreversible adsorption in glassy polymeric domain. *Environ. Sci. Technol.* **52**, 2677–2685 (2018).
41. Fiorentino, I. *et al.* Energy independent uptake and release of polystyrene nanoparticles in primary mammalian cell cultures. *Exp. Cell Res.* **330**, 240–247 (2015).
42. Moore, M. N. *et al.* Antagonistic cytoprotective effects of C60 fullerene nanoparticles in simultaneous exposure to benzo[a]pyrene in a molluscan animal model. *Sci. Total Environ.* **755**, 142355 (2021).
43. Behzadi, S. *et al.* Cellular uptake of nanoparticles: Journey inside the cell. *Chem. Soc. Rev.* **46**, 4218–4244 (2017).
44. Cajaraville, M. P. & Pal, S. G. Morphofunctional study of the haemocytes of the bivalve mollusc *Mytilus galloprovincialis* with emphasis on the endolysosomal compartment. *Cell Struct. Funct.* **20**, 355–367 (1995).
45. Lehner, R., Weder, C., Petri-Fink, A. & Rothen-Rutishauser, B. Emergence of nanoplastic in the environment and possible impact on human health. *Environ. Sci. Technol.* **53**, 1748–1765 (2019).
46. Banerjee, A. & Shelver, W. L. Micro- and nanoplastic induced cellular toxicity in mammals: A review. *Sci. Total Environ.* **755**, 142518 (2021).
47. Rejman, J., Oberle, V., Zuhorn, I. S. & Hoekstra, D. Size-dependent internalization of particles via the pathways of clathrin- and caveolae-mediated endocytosis. *Biochem. J.* **377**, 159–169 (2004).
48. Johnston, H. J. *et al.* Evaluating the uptake and intracellular fate of polystyrene nanoparticles by primary and hepatocyte cell lines in vitro. *Toxicol. Appl. Pharmacol.* **242**, 66–78 (2010).
49. Kuhn, D. A. *et al.* Different endocytotic uptake mechanisms for nanoparticles in epithelial cells and macrophages. *Beilstein J. Nanotechnol.* **5**, 1625–1636 (2014).
50. Gedda, M., Babele, P., Zahra, K. & Madhukar, P. Epigenetic aspects of engineered nanomaterials: Is the collateral damage inevitable?. *Front. Bioeng. Biotechnol.* **7**, 228 (2019).
51. Batel, A., Linti, F., Scherer, M., Erdinger, L. & Braunbeck, T. The transfer of benzo[a]pyrene from microplastics to *Artemia nauplii* and further to zebrafish via a trophic food web experiment—CYP1A induction and visual tracking of persistent organic pollutants. *Environ. Toxicol. Chem.* **35**, 1656–1666 (2016).
52. Salvati, A. *et al.* Experimental and theoretical comparison of intracellular import of polymeric nanoparticles and small molecules: Toward models of uptake kinetics. *Nanomedicine* **7**, 818–826 (2011).
53. Fröhlich, *et al.* Action of polystyrene nanoparticles of different sizes on lysosomal function and integrity. *Part. Fibre Toxicol.* **9**, 26 (2012).
54. Wu, B., Wu, X., Liu, S., Wang, Z. & Chen, L. Size-dependent effects of polystyrene microplastics on cytotoxicity and efflux pump inhibition in human Caco-2 cells. *Chemosphere* **221**, 333–341 (2019).
55. Stock, V. *et al.* Uptake and effects of orally ingested polystyrene microplastic particles *in vitro* and *in vivo*. *Arch. Toxicol.* **93**, 1817–1833 (2019).
56. Sharifi, S. *et al.* Toxicity of nanomaterials. *Chem. Soc. Rev.* **41**, 2323–2343 (2012).
57. Hwang, J., Choi, D., Han, S., Choi, J. & Honga, J. An assessment of the toxicity of polypropylene microplastics in human derived cells. *Sci. Total Environ.* **684**, 657–669 (2019).
58. Gómez-Mendikute, A., Etxeberria, A., Olabarrieta, I. & Cajaraville, M. P. Oxygen radicals production and actin filament disruption in bivalve haemocytes treated with benzo(a)pyrene. *Mar. Environ. Res.* **54**, 431–436 (2002).
59. Gómez-Mendikute, A. & Cajaraville, M. P. Comparative effects of cadmium, copper, paraquat and benzo[a]pyrene on the actin cytoskeleton and production of reactive oxygen species (ROS) in mussel haemocytes. *Toxicol. In Vitro* **17**, 539–546 (2003).
60. Ji, Y., Wang, Y., Shen, D., Kang, Q. & Chen, L. Mucin corona delays intracellular trafficking and alleviates cytotoxicity of nanoplastic-benzopyrene combined contaminant. *J. Hazard. Mater.* **406**, 124306 (2021).
61. Rossi, G., Barnoud, J. & Monticelli, L. Polystyrene nanoparticles perturb lipid membranes. *J. Phys. Chem. Lett.* **5**, 241–246 (2014).
62. Jiménez, M., Aranda, F. J., Teruel, J. A. & Ortiz, A. The chemical toxic benzo[a]pyrene perturbs the physical organization of phosphatidylcholine membranes. *Environ. Toxicol. Chem.* **2**, 787–793 (2002).
63. Katsumiti, A., Gilliland, D., Arostegui, I. & Cajaraville, M. P. Cytotoxicity and cellular mechanisms involved in the toxicity of CdS quantum dots in hemocytes and gill cells of the mussel *Mytilus galloprovincialis*. *Aquat. Toxicol.* **153**, 39–52 (2014).
64. Katsumiti, A. & Cajaraville, M. P. *In vitro* toxicity testing with bivalve mollusc and fish cells for the risk assessment of nanoparticles in the aquatic environment. In *Ecotoxicology of Nanoparticles in Aquatic Systems* (eds Blasco, J. & Corsi, I.) 62–98 (Science Publishers CRC Press/Taylor & Francis Group, 2019).
65. May, R. C. & Machesky, L. M. Phagocytosis and the actin cytoskeleton. *J. Cell Sci.* **114**, 1061–1077 (2001).
66. Revel, M. *et al.* Tissue-specific biomarker responses in the blue mussel *Mytilus spp.* exposed to a mixture of microplastics at environmentally relevant concentrations. *Front. Environ. Sci.* **7**, 1–14 (2019).
67. Cajaraville, M. P., Pal, S. G. & Robledo, Y. Light and electron microscopical localization of lysosomal acid hydrolases in bivalve haemocytes by enzyme cytochemistry. *Acta Histochem. Cytochem.* **28**, 409–416 (1995).
68. Espinosa, C., García, J. M., Esteban, M. A. & Cuesta, A. *In vitro* effects of virgin microplastics on fish head-kidney leucocyte activities. *Environ. Pollut.* **235**, 30–38 (2018).
69. Banni, M. *et al.* Assessing the impact of benzo[a]pyrene on marine mussels: Application of a novel targeted low density microarray complementing classical biomarker responses. *PLoS ONE* **12**, e0178460 (2017).
70. Canova, S. *et al.* Tissue dose, DNA adducts, oxidative DNA damage and CYP1A-immunopositive proteins in mussels exposed to waterborne benzo[a]pyrene. *Mutat. Res.* **399**, 17–30 (1998).
71. Tung, E. W., Philbrook, N. A., Belanger, C. L., Ansari, S. & Winn, L. M. Benzo[a]pyrene increases DNA double strand break repair *in vitro* and *in vivo*: A possible mechanism for benzo[a]pyrene-induced toxicity. *Mutat. Res.* **760**, 64–69 (2014).
72. Bihari, N., Batel, R. & Zahn, R. K. DNA damage determination by the alkaline elution technique in the haemolymph of mussel *Mytilus galloprovincialis* treated with benzo[a]pyrene and 4-nitroquinoline-N-oxide. *Aquat. Toxicol.* **18**, 13–22 (1990).
73. Ribeiro, F. *et al.* Microplastics effects in *Scrobicularia plana*. *Mar. Pollut. Bull.* **122**, 379–391 (2017).
74. Brandts, I. *et al.* Effects of nanoplastics on *Mytilus galloprovincialis* after individual and combined exposure with carbamazepine. *Sci. Total Environ.* **643**, 775–784 (2018).
75. Maria, V. L., Gomes, T., Barreira, L. & Bebianno, M. J. Impact of benzo(a)pyrene, Cu and their mixture on the proteomic response of *Mytilus galloprovincialis*. *Aquat. Toxicol.* **144–145**, 284–295 (2013).
76. Bellas, J. *et al.* Combined use of chemical, biochemical and physiological variables in mussels for the assessment of marine pollution along the N-NW Spanish Coast. *Mar. Environ. Res.* **96**, 105–117 (2013).

77. Katsumiti, A., Tomovska, R. & Cajaraville, M. P. Intracellular localization and toxicity of graphene oxide and reduced graphene oxide nanoplatelets to mussel hemocytes in vitro. *Aquat. Toxicol.* **188**, 138–147 (2017).

Acknowledgements

This work was carried out within the EU Project PLASTOX (JPI Oceans 005/2015) and was funded by the Spanish MINECO (NACE Project, CTM2016-81130-R) and Basque Government (Consolidated Research Groups Grant IT1302-19).

Author contributions

M.P.C. developed the project idea and obtained funding. M.P.C. and A.K. designed the experiments and supervised student's work. M.P.L.C., A.K. and M.B. performed the experiments. The manuscript was written by A.K., M.P.C. and M.P.L.C. and revised by all authors.

Competing interests

The authors declare no competing interests.

Additional information

Supplementary Information The online version contains supplementary material available at <https://doi.org/10.1038/s41598-021-01938-4>.

Correspondence and requests for materials should be addressed to M.P.C.

Reprints and permissions information is available at www.nature.com/reprints.

Publisher's note Springer Nature remains neutral with regard to jurisdictional claims in published maps and institutional affiliations.



Open Access This article is licensed under a Creative Commons Attribution 4.0 International License, which permits use, sharing, adaptation, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons licence, and indicate if changes were made. The images or other third party material in this article are included in the article's Creative Commons licence, unless indicated otherwise in a credit line to the material. If material is not included in the article's Creative Commons licence and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder. To view a copy of this licence, visit <http://creativecommons.org/licenses/by/4.0/>.

© The Author(s) 2021